SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1906, by Munn & Co.]

Vol. XCIV.—No. 16.
ESTABLISHED 1845.

NEW YORK, APRIL 21, 1906.

[10 CENTS A COPY
$3.00 A YEAR.



Section Through Round Door and Wall of Armor-Plate Vault.



Section Through Rectangular Door and Wall of Laminated Five-Ply Vault.



The Lower Vault, 20 Feet by 20 Feet by 9 Feet, is Built of Laminated Five-Ply Welded Steel and Iron; with 6-Inch Walls and 12-Inch Doors. The Upper Vault, 23 Feet by 20½ Feet by 10 Feet, is Built of Harveyized Nickel-Steel Armor Plate Weighing 200 Tons. Door Weighs 16 Tons.

ARMOR PLATE—THE LAST ANSWER OF THE BANKER TO THE BURGLAR.—[See page 325.]



SCIENTIFIC AMERICAN

ESTABLISHED 1845

MUNN & CO., - - Editors and Proprietors

Published Weekly at

No. 361 Broadway, New York

TERMS TO SUBSCRIBERS

One copy, one year for the United States, Canada, or Mexico $3.00
One copy, one year, to any foreign country, postage prepaid. £0 16s. 5d. 4.00

THE SCIENTIFIC AMERICAN PUBLICATIONS.

Scientific American (Established 1845) ..... $3.00 a year
Scientific American Supplement (Established 1876) ..... 5.00 "
American Homes and Gardens ..... 3.00 "
Scientific American Export Edition (Established 1878) ..... 3.00 "

The combined subscription rates and rates to foreign countries will be furnished upon application.

Remit by postal or express money order, or by bank draft or check.

MUNN & CO., 361 Broadway, New York.

NEW YORK, SATURDAY, APRIL 21, 1906.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are *sharp*, the articles *short*, and the facts *authentic*, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

INTERNATIONAL PROTECTION OF NIAGARA FALLS.

Joint international action by the United States and Canada for the preservation of the scenic beauties of Niagara Falls is an assured fact. Representative Burton, of Ohio, has laid before Congress a proposition for diplomatic action with Great Britain which, in the event of favorable action, will give the Secretary of War authority to grant revocable permits for diversion of water from Niagara River "only to individuals, companies, or corporations, which are now actually producing power from said water, and to them only to the amount now actually in use by such individuals, companies, or corporations." On the other hand, the Canadian Minister of Public Works has announced at the Canadian capital a federal policy to preserve Niagara Falls. Under this policy the right to export electric energy into the United States will be granted under the understanding that it can be revoked at short notice, and that there shall be no claim against the government arising out of such revocation, and, moreover, that the companies shall be subject to such regulations as the government may impose. It seems that, as far as the Canadian side is concerned, the export of power to the United States is the most serious danger confronting the Falls, and the fact that the Canadian government should so soon have placed an embargo on exportation may be taken as evidence of its desire to co-operate with the United States in this important matter.

THE ENGLISH CHANNEL TUNNEL.

It is natural that the friendly relations lately established between Great Britain and France should encourage the promoters of the project for a tunnel beneath the English Channel to make another effort to obtain the necessary sanction of the British government. The Société Français du Tunnel Sous-Marin was incorporated in the early seventies for the purpose of carrying out this great work. A shaft was sunk on the French side of the Channel at a point about six miles from Calais, and the English terminus was fixed near to Dover. A considerable amount of tunneling was done by the French company; but after they had spent about half a million dollars, the British government put a stop to the work on the English end, ostensibly for the reason that a tunnel beneath the Channel would destroy the security which Great Britain's insular position afforded, and would render her liable to attack by an invading army.

Engineers of the Northern Railway of France have recently made an investigation of the abandoned works and found them to be in good condition, and it is probable that the present session of Parliament will witness the introduction of a bill for permitting the work to proceed on the English side. The tunnel would be an ideal one to drive, as practically the whole of its 23½ miles of length will pass through a firm but easily-quarried chalk, which it is believed is free from faults. This would make it possible to drive the tunnel without the use of the pneumatic process, or the necessity for serious pumping operations. Apart from military considerations which, in themselves, cannot have much weight because of the tunnel's limited capacity and ease of destruction, there is much to be said in favor of the proposed tunnel. The Dover-Calais passage is notoriously rough and uncomfortable, and the substitution of an all-rail route between London and Paris would be a decided boon to hundreds of thousands of travelers between England and the Continent.

ELECTRIC EQUIPMENT OF A GREAT RAILROAD.

The magnitude of the work involved in the equipment of the New York Central terminal and suburban lines looms so large before the public that the great work of electrically equipping the New Haven system is scarcely receiving the attention it deserves. This important four-track system is to be operated from the Grand Central station terminal to Stamford entirely by electric locomotives, and the work of equipping the line and constructing the rolling stock is being rapidly pushed forward with a view to the earliest possible operation of the road. The problem confronting the New Haven company has been complicated by the fact that they have decided to use the single-phase alternating current, although for a considerable distance the trains must run over the tracks of the New York Central company, which are to be equipped with the direct current. The motors will be so constructed that they can run on single-phase current on the lines of the New Haven company, and then make use of the direct current from Woodlawn to the Grand Central Station, running as direct-current motors over the 11 miles intervening between those points, the power for train operation being purchased from the New York Central. East of Woodlawn the trains will take current from a new power station which is being built by the New Haven company at Cos Cob. The steam-generating equipment will consist of 9,000-horse-power water-tube boilers, which will supply steam to 3,000-kilowatt Parsons steam turbines. The generators will supply single-phase, 25-cycle, 11,000-volt current; but they will be so wound that, if it is desired, they can deliver three-phase current. Power will be distributed at the high potential of 11,000 volts, and therefore no step-up transformers will be needed. Instead of the customary third rail, overhead wires will be used. The locomotives will be of the Westinghouse type, and will weigh about 72 tons each, and all of the axles will be used as driving axles. The locomotive will be carried upon two trucks, each of which will be equipped with two 250-horse-power single-phase, gearless motors. An important feature in the suspension is that the weight of both the armature and the field is spring-supported. The figures of cost of the installation are interesting as showing the relative expenditure that must be made upon power house, overhead lines, and locomotives, the power house costing $1,130,000, the line, of which there will be 21 miles four-track, costing $570,000, and the locomotives $1,050,000. It is probable that the success of this first installation will be followed by similar equipment of zones extending around other principal cities on the New Haven system. Ultimately the extension of these zones to a junction with one another will eliminate the steam locomotive, and leave the whole system to electric operation. Because of its vast suburban and interurban business, we think that the New Haven system is perhaps better placed for the wholesale application of electric traction than any other of the large trunk roads of the country.

UNIFORMITY IN BATTLESHIPS.

It has long been recognized by naval men that a fleet which is made up of heterogeneous types of ships, that is of ships of different size, speed, armament, and protection, is at a great disadvantage from a tactical point of view when it encounters a fleet of the same total displacement whose ships are arranged in groups of identical vessels. Recent naval operations have emphasized very strongly the truth of this principle, and the best-organized navies of to-day are building their ships in groups or classes of four, six, or eight. Ships of such a group have the great advantage that their speed, their coal endurance, and their turning diameter are identical, and that in the various evolutions the vessels will, in their new positions, find themselves at all times grouped symmetrically.

It is earnestly desired by our Navy Department that when new ships are authorized, they shall conform to some existing design until they have been brought up to the proper number of units to form a class, say of half a dozen; and they are naturally opposed to the construction of any new type of vessel which is not likely to be repeated sufficiently often to form a new group.

The decision of the House Committee on Naval Affairs to recommend an appropriation for the construction of a battleship which, in size and power, will surpass any ship at present under construction, has naturally appealed to the non-professional world, or rather to that section of it which believes that there is a certain national prestige conveyed by the possession of a "world-beater"; but our naval constructors, who have learned to subordinate sentiment to reason and cold facts, look very unfavorably on the proposition. They are well aware that, although we are perfectly well able to build a 20,000-ton ship of 20 knots speed, such a vessel would be in a class all by itself, and, when maneuvering in the company of smaller, slower, and less powerful ships, would have to accommodate herself to their limitations, and therefore would be unable to realize in action her full efficiency. The plans proposed for our latest ships, the "Michigan" and "South Carolina," will give us a magnificent ship, of which we ought to build at least half a dozen before launching out into new types.

Although our earlier battleships differ widely in type, our later ships resolve themselves into classes, each composed of about five or six units. Thus, the three ships of the "Maine" type and the three of the "Illinois" type give us a class of six approximately similar ships. In the "Virginia" class we have five ships absolutely identical; in the "Louisiana," "Vermont," and "New Hampshire" classes we have six practically identical battleships in which the "Mississippi" and "Idaho," were it not for their low speed, might possibly be included, bringing the number up to eight; while in the "South Carolina" and "Michigan," our latest designs, we have a class which, as we have said, should be extended until it includes five or six identical vessels. By the time Congress has made sufficient appropriation for this purpose, the Navy Department will have formulated its ideas as to the best type of vessel to build, if we decide to construct ships of 18,000 to 20,000 tons displacement.

But it will be an unhappy day for the Navy Department if the Bureau of Construction is to be controlled by any popular "whip creation" theories of warship construction.

THE DEVELOPMENT OF AERIAL NAVIGATION FOR MILITARY PURPOSES IN EUROPE.

Owing to the success that has attended the various trials carried out by the French military authorities with the Lebaudy airship, aerial navigation for military purposes is being rapidly developed upon an extensive scale by the prominent European powers. France is particularly energetic in this direction, and has now adopted another airship (the invention of M. Juillot, an engineer in the army) the experiments with which have been conspicuously successful. Under these circumstances the War Department realizes that the time has come when the development of this new scientific aid to military operations should be carried out upon an organized basis. For this purpose there has been initiated a corps of "balloon scouts," the members of which are to be drawn from the officers in the army whose examinations demonstrate their capacity for the work of the new department. The "*observateurs en ballon*," as they are officially designated, will not act as aeronauts simply, but are to be employed more for strategical work, for which their training in the field and siege artillery sections renders them especially serviceable. The inauguration of this special corps is the outcome of the successful reconnoitering operations that were carried out from the Lebaudy airship during its trip along the eastern frontier.

The members of this corps will be selected on account of their light weight, particularly good sight, and their proficiency in rapid and accurate topographical drawing, since their operations will be confined mostly to the acquisition of information of an enemy's position both before and during an action and the conveyance of such information to headquarters. The aerostats are provided with a full equipment for accomplishing this end. The members of this corps will pass through three months' training in military aeronautics with the special battalion of aeronaut engineers.

In Great Britain, also, military ballooning is being rapidly developed and extended. The balloon factory at Aldershot is to be completely overhauled, and $50,000 expended in new equipment during the coming year. Owing to the success that has attended the experiments that have been carried out by the War Office with the Cody man-lifting kites, a special instructor for this work has been appointed at a salary of $3,000 per annum, and the kite-flying division will constitute a section of the balloon department.

Several improvements have been effected during the past few months with the Cody kites, the inventor having been retained by the War Office for the work of initiating the men into the work. The results achieved have been completely successful, the basket attached to the kites easily lifting a man of 240 pounds in weight to a height of 3,000 feet. Owing to the steadiness with which the kites ride in the air surveying and drawing by the officer in the basket can be easily and comfortably carried out, while messages can be carried between the surveyor and the ground station by means of the telephone carried by the wire.

The department is now engaged in experiments with a "glider," which has been devised by Capt. Cody. This comprises a long double-banked framework of bamboo, upon which is stretched calico. The wings are long and narrow, and arranged one above the other on either side of the body in much the same way as the wings of a dragon fly. The aeroplanes, however, are quite stationary. Along the front edge, however, is a slight curvature, which can be lessened or increased as desired by the operator, who lies prone in a net slung beneath the center or body of the machine. The glider is released from an eminence or balloon in much the same way as a parachute, and the operator is able to regulate his descent by the manipulation of the wings. The greatest height from which this glider has been released is 500 feet, and the aeronaut has successfully glided a distance of half a mile before coming to earth. Experiments have shown that it is possible to descend from this elevation to any desired point, even the sharpest descents in point of angle being accomplished

without any injury to the operator. Flights from higher elevations are to be carried out, but for these the aeroplane is to be provided with a tail piece, which it is anticipated will enable the machine to be more easily controlled.

During the next few months, also, the first trials with the dirigible airship invented by Col. Templer, the head of the war ballooning department, are to be carried out. The inventor has been engaged upon this aerostat for several years past, and has been assisted in his efforts by the War Department. The design of this aerostat follows the usual lines, comprising a cigar-shaped gas vessel 140 feet in length by 25 feet in diameter at the center. Its capacity is about 70,000 cubic feet of hydrogen, and the lifting power is over 6,750 pounds, though the structure itself weighs 1,200 pounds. It is most strongly constructed, the material of the gas envelope being of great thickness, so as to resist tearing and cracking. It is ribbed diagonally and inclosed in a network of fine cord. So stoutly is the envelope constructed, that when inflated the balloon is as solid as a football, and one can walk over it without making the slightest indentation.

Forty feet below the gas bag is suspended a light wicker frame-work shaped like a whaleboat. This carries the 40-horse-power gasoline motor sets, which are of special type, and the disposition of which is carried out upon novel lines. At either end of the frame-work are placed the propellers, the experiments with which show that in calm weather a speed of twenty miles an hour should be attained. The steering of the airship is effected upon novel lines. The construction of this vessel has been carried on with great secrecy in a house specially provided for the purpose. The vessel is, however, now completed, and the trials will take place at the first favorable opportunity. The vessel has been three years under construction, and the inventor has been able to eliminate those features which experiments by other inventors during this period have proved to be either unsatisfactory or useless.

The German military department has also decided to exploit the subject. The work, however, will not be carried out by the government, but by private enterprise, a company having been especially incorporated in Berlin under the influence of the Kaiser for this purpose. The object of this company will be to examine and test the various airships constructed in the anticipation that one suitable to military requirements may be discovered.

CANALS AND RAILWAYS IN INDIA.

BY L. H. YATES.

Some important facts and figures relating to the respective values of canals and railways in India were laid before the Society of Arts, London, quite recently. Mr. R. B. Buckley, C.S.I., wished to point out that there ought not to be any rivalry between the two modes of transit, when rightly and fairly considered, and others who spoke after his paper had been read indorsed this opinion. Both methods are necessary for the full development of a country, and both tend to increase the total volume of trade. The point where friction arises in India is that the government readily grants free land to the railway companies, and guarantees the payment of interest on their capital outlay, while the navigation companies can obtain no help at all, and, save in a few instances, the government is unwilling to spend anything on maintaining even the original great waterways.

Making a few comparisons between railways and canals, with reference to their profit to the state, the reader of the paper pointed out that the Bengal Central Railway, since its opening in 1881, has been worked at a gross loss of £400,000, after the guaranteed interest of 3½ per cent has been paid. During the same period, the Calcutta and Eastern canals, taking interest at the same rate, had worked at a profit to the state of £25,000. "This," said he, "is a fair case in which a canal working side by side with a railway has held its own against competition, and the example gives force to the contention that it is to the interest of a country that money should be spent on navigable waterways." He did not grudge the expenditure of 235 millions on the railways of India in the last half century, but the five millions spent on her waterways had been totally inadequate and disproportionate. The Assam-Bengal Railway provides another instance of unequal treatment. The trade which passes between Bengal and Assam is, next to the domestic trade of Bengal itself, the most important of the whole country, and roughly speaking, one-third goes by rail and two-thirds by water. The railway runs through from Chittagong to Johat and Dibrughur, and will in a short time be connected with Calcutta. While it is of great benefit and convenience, it is worked at a heavy loss to the state, though constructed and worked by a company, with a guarantee of 3 per cent interest payment. The capital expended by the end of 1904 amounted to £8,400,000, and after meeting interest charges the loss on the working of the line was in 1905, £93,000; in 1900 it was £200,000; and in 1904, £270,000. "This," said Mr. Buckley, "is an example of the price which the state pays from the general revenues, for benefits which the railway is supposed to confer."

The Honorable East India Company was the first to organize steam traffic on the Bengal waterways, and so far back as 1834 the business had become a very profitable one, and by then a regular line of steamers was running from Calcutta to Allahabad. Now the traffic is worked by different companies, with large fleets of steamers and flats. These companies have no guarantee on their capital and receive no contribution from the state toward the payment of their interest, but during the years in which eight millions sterling have been spent on the construction of the Assam-Bengal line, the only large improvement here made, that on the Bhil route, has cost £50,000, and this brought in last year a direct net revenue of about £2,500, or 5 per cent on its cost. No doubt the returns from the railway will improve in time, and the reasons which determined its construction were, perhaps wisely, largely independent of its financial success, but the marked difference between it and the treatment of the navigation companies has led to much sore feeling, in consideration of their respective returns.

The greater number of the canals in India have, of course, been primarily constructed for irrigation—for the preservation and improvement of agricultural crops. But in a number of cases the main canals have been so constructed that they might be used for navigation as well as for irrigation, and there are three important canals in India which have been constructed for navigation only, with several minor ones of the same class. About one-fourth of the aggregate length of irrigation canals in India has been made navigable. The cost of the purely navigation canals has been about a million and a half sterling. These canals are in immediate contact with the tidal creeks and rivers connected with the Bay of Bengal; indeed, the greater portion of the Circular and Eastern Canal, which connects Calcutta and Barisaul in Eastern Bengal, consists of natural tidal channels artificially improved. The Calcutta and Eastern Canal is in many respects a remarkable work, not only in construction, but because it is one of the few instances where the government has itself undertaken to improve it by outlay of money. The canal itself runs generally east and west, while the various channels, or "gongs," as they are called, which are connected with the Bay of Bengal, run generally north and south. These gongs are mostly tidal, so that the general ebb and flow of the tide is more or less at right angles with the line of the canal. The main channels are linked together by an intricate system of cross streams, which intersect the forest of the Sunderbunds in all directions, so that it is always possible to find a way from one gong to another. The canal has, in fact, utilized a system of cross channels between the main gongs to some extent; in other instances artificial cross channels have been made.

It has been maintained that it is at least desirable, if not necessary, to make the trunk lines of an irrigation system navigable, in order that an easy and cheap means of transit may be provided for grain and other crops. It is said that the expense of the additional work is not large, while the convenience to the people is very great. But after going into the question at considerable length, and giving the various causes which make for and against the feasibility of altering the construction from one system to another, Mr. Buckley had reached the conclusion that, taking all things into consideration, the difference of cost between a canal designed purely for irrigation, and one adapted from that for navigation also, is from £1,500 to £2,000 per mile. The profits on navigable waterways are almost solely found on the purely navigation canals. The Orissa Coast, the Calcutta and Eastern, and the Buckingham Canal, bring in more revenue than all the others combined. The obvious reason for this is that the navigation canals follow trade routes, while canals designed primarily for irrigation do not. The latter, when navigable, are useful to the people whose villages are near them, but seeing that, taken collectively, the irrigation systems of India pay 7 per cent on their cost, it should hardly be a matter for objection if in one function they are not altogether satisfactory. On all Indian canals tolls are charged on the boats which use them. It may not be strictly accurate to say that in all countries save England and India the canals are free, but it is true in the main. In France, in Italy, and in Austria-Hungary (with the exception of the Iron Gates Canal) no tolls are levied on navigation; in Belgium and Germany, though tolls are charged, they are very low; in the United States and Canada all are free save those which are not the property of the state. In Egypt tolls were abolished in 1901. It would seem as if the time had come when the government of India should consider the desirability of leaving the navigation of the canals as free as is the traffic of the roads.

It was pointed out by a speaker, after the reading of Mr. Buckley's paper, that the greatest service rendered by the smaller canals was that of providing roads in districts where roads on land were difficult to maintain. Small canals between rivers would serve really important agricultural districts much better, indeed, than roads, and in thus catering for local interests there was a much better prospect for their becoming financially successful than in any attempt to make them compete with rival routes and leading lines.

A writer on the subject of "British Canals" said that where canals do not pay *per se*, they pay by increasing the volume of trade. This was the reason why France and Germany found it profitable to spend so largely on the development of their canal systems, and the trade increase they could show was the proof. In the case of the Manchester Ship Canal, this was strikingly brought out; in itself it was a failure, financially considered, but since its opening and working an enormous number of industries had sprung up which could never have arisen had not the canal been there first, and so it was with many other canals. If a community benefited as a whole by the expenditure made upon these objects, there ought to be no thought of antagonism as to the respective merits of each means; all deserved their share of support, and from the state at least, all deserved equal consideration.

MOSQUITO EXTERMINATION.

This is another name for the prevention of mosquito breeding by obliterating the primary conditions requisite for their wholesale production. On the 11th instant the Third Annual Convention of the American Mosquito Extermination Society was held in this city, at the New York Aquarium, and supplemented in the evening by a dinner given at the Union League Club by the President, Mr. Wm. J. Matheson, in honor of several guests and Health Board officials.

At the convention it was shown that much progress had been made toward the abatement of the mosquito nuisance by a greater enlightenment of public sentiment in its favor, as evidenced through recent legislative enactments.

In the State of New Jersey, for example, where only a few years ago the suggestion of eliminating the mosquito met with ridicule, now, as a result of a more universal education and extension of information on the subject, it is reported that the State Legislature has passed almost unanimously an appropriation of $350,000, to be expended at the rate of $50,000 per year for the diking and ditching of the great salt marshes lying adjacent to the city of Newark and about the Hackensack River. Legislation is also in process in the New York Legislature to the same end for the benefit of New York city.

The convention adopted what is termed a "Mosquito Brief," stating in simple language the number of species of mosquitoes that inhabit marsh lands and cesspools of the United States—that they can only breed in water; that one mosquito can lay on the average three hundred eggs a day; that the life of one mosquito is about a month. The most dangerous of Southern mosquitoes is the *Stegomyia fasciata*, the natural carrier of yellow fever germs.

At the evening dinner, Gen. Fred D. Grant, of Governor's Island, U. S. army post, gave some interesting reminiscences on mosquitoes and their effect on the health of the army. He related how he had protected a division of the army located on one side of the Rio Grande River, in a southern section of the country, from the spread of yellow fever, which had broken out in a town situated on the opposite bank. He secured funds from Washington to carry out an effective system of screening, and said as a result that not one of his men was taken with the fever. On Governor's Island, numerous relics in the shape of 15-inch-gun shells were inverted, so as to shed water instead of holding it, which had the effect of relieving locally the generation of the insects. Even upright rifle barrels were filled with sand to avoid the collection of water.

Mr. Paul D. Cravath related an interesting record concerning the relation of the mosquito to malaria. On the north side of Long Island, about thirty miles from New York, there were certain valleys and bays where the mosquito was notoriously evident. The areas were located upon a map. Another record was made as to the extent of malaria over this section, from physicians and others, and these areas were placed upon a second duplicate map. This medical map was then superimposed over the first map, and it was found the areas in both cases pretty evenly matched each other.

This record is of special interest to all boards of health, and proves most graphically how it is possible to improve the public health by the prevention of mosquito breeding.

Other interesting remarks were made, showing how marshy places by being reclaimed and converted into public parks could easily improve land valuations and at the same time become a public benefit.

The United States gasoline torpedo is now an official weapon. Its speed is 36 knots.

THE BELL TETRAHEDRAL KITE IN WIRELESS TELEGRAPHY.

The announcement has recently been made by the American De Forest Wireless Telegraph Company of the successful transmission of messages from Manhattan Beach, Long Island, to Glengarriff harbor, County of Cork, Ireland. The station at Manhattan Beach, which was only quite recently completed, has a 40-kilowatt (54-horse-power) equipment. The current is stepped up to a pressure of 30,000 volts. The aerial is supported by masts 210 feet high. At Glengarriff the messages were received on aerials supported by kites. It is interesting to note that the first wireless signal across the Atlantic, that of Marconi in 1901, was also received by means of a kite-supported aerial at St. Johns, Newfoundland. In fact, Marconi's original patent suggested the use of kites or captive balloons to support the aerials. His idea then, however, was to coat the kite or balloon with tinfoil or some other metallic substance, so that it would afford an inductive capacity at the upper end of the antenna. Such a capacity is now no longer considered of any great benefit, and is not used on any of the present systems. The advantage of a kite or balloon support is that it will carry the aerial to a much greater height than is possible with a fixed mast. The antennæ will then intercept waves which are too high to be affected by earth currents. The reason kites have not been more universally adopted is that they are usually rather uncertain in their action. A sudden squall or a change in the direction of the wind will send them swooping toward the ground. A balloon offers the same disadvantages, with the additional one that the gas is liable to leak out and permit the aerial to drop to the ground. In the Marconi experiments hexagonal kites were used. Tests have also been made with tailless Malay kites and Blue Hill box kites. All of these, however, are open to the same objections of unsteadiness and unreliability.

In the De Forest experiments the effort was made to discover a kite which would ride steadily under the most adverse conditions. These desiderata were found in Prof. Alexander Graham Bell's tetrahedral kites. We have recently described Prof. Bell's kites very fully, and a further description of them here is not necessary. Suffice it to say that they are made up of series of cells consisting of triangular pyramidal skeleton frames, two sides of each pyramid or tetrahedron being covered with silk, while the others are left open. With this construction Prof. Bell found that a perfect equilibrium could be maintained. The kite rode steadily in the air, and did not swing from side to side or dive suddenly when struck by a squall. Even when released it maintained its equilibrium, and settled slowly and gently to the ground without oscillating.

Before carrying on experiments with transatlantic wireless telegraphy, tests of these kites were made at Arlington, Va. The accompanying illustrations are reproductions of photographs taken at these tests. One of the photographs shows the pilot kite, which was sent up to determine atmospheric conditions in the upper strata of air before the main kite was sent up. The antenna wire was attached to the kite wire, and carried up to heights ranging from 1,000 to 2,000 feet. Both aluminium and light copper wire were tried. At this altitude messages were easily picked up from vessels many miles out at sea and from stations all along the coast. It was found that the kites flew steadily, and could be kept in the air continuously day and night regardless of changes in the direction of the wind. An attendant had to pay out the line or reel it in as required, but no other attention was necessary. Occasionally a rain storm would wet the kite, and increase its weight sufficiently to drag it down. But as it fell, the kite wire would be reeled in, and a level would finally be reached where the weight of the wire reeled in would compensate for the increased weight of the water-soaked silk, and at this level the kite would remain. The experiments proved that the kites were proof against all conditions except a snow storm, which might weigh it down, or a violent gale or hail storm, which might destroy it. The purpose of the experiments at Glengarriff was to facilitate attuning the station at that point with the one at Manhattan Beach. After the necessary attunement has been attained, it is expected that messages can be easily transmitted to aerials supported by stationary masts. The kite-supported aerials are, therefore, experiments of a temporary nature. It is expected that kite-supported aerials will prove of great value for temporary stations, such as would be necessary in reporting a yacht race, for example, or some other event in a locality where it would be inexpedient to establish a permanent station.



Copyright, 1906, by Waldon Fawcett.

Using the Kite Wire for an Antenna.



1. Prof. Bell's New Kite for Wireless Telegraph Experiments. 2. Small Pilot Kite Sent Up in Advance of Main Kite. 3. Receiving Messages with a Kite-Supported Aerial. 4. End View of the Tetrahedral Kite.

Copyright, 1906, by Waldon Fawcett.

THE BELL TETRAHEDRAL KITE IN WIRELESS TELEGRAPHY.

Although the chemical methods of estimating the strength of wheat have as yet proved inconclusive, some idea of the factors determining this quality has been reached from practical baking tests combined with measurements of the gluten and nitrogen content of the flour. In the first place manuring proves a very small factor; it is found that the composition of the grain of wheat is extraordinarily stable and the plant reacts to diversities in nutrition by producing more or less grain rather than by altering its composition. Even under the exceptionally pronounced variations in the manurial conditions of the Rothamsted plots, the composition of the grain fluctuates more with changing seasons than with changed manuring. Within the limits of healthy growth and ripening the date of sowing the wheat has no effect upon the quality of the grain; the same wheat sown at monthly intervals from October to March gave practically identical quality in the grain, and a number of comparisons between autumn and spring sowing led to no definite conclusion.

ARMOR PLATE—THE LAST ANSWER OF THE BANKER TO THE BURGLAR.

The banks and trust companies are steadily raising the standard of excellence required in the construction of their vaults. Time was when the term "burglar-proof" stood for the high-water mark of vault construction; and the vault which could not withstand the attack of a first-class cracksman, operating under normal conditions, was not considered to be of a quality entitled to be called first-class. To-day, however, the demand is being made that a vault shall be able to resist attack under abnormal conditions. It might happen that through the distraction caused by a city conflagration, or the failure of the civil authorities to exercise their power, the professional cracksman or the lawless element might find themselves in a position to operate upon a safe without fear of immediate detection. Under these conditions they could bring to bear methods of attack which would be impossible under normal conditions; and the financial institutions are demanding that the modern vault shall be proof even against this. Moreover, events in Russia have shown that although this is an age of advanced civilization, it is possible for communities to fall into the hands of rioters and remain in their control for days together, and it requires but little imagination to foresee a leader directing a mob to the accumulated treasure of others. The great wealth stored in vaults must, in such a case, become a natural object of attack, and with unlimited time and means at command, they would be subjected to treatment which the mere burglar-proof construction could never withstand. It was in the search for special material and methods of construction that would be proof even against such a contingency, that the vault engineer was finally led to turn his attention to the question of using face-hardened Harveyized armor plate.

As the readers of the SCIENTIFIC AMERICAN are well aware, we have at various times illustrated the manufacture of armor plate, and explained the special qualities which enable it to present such great resisting qualities to the attack of high explosives and large-caliber projectiles. In the following article we propose to trace, briefly, the development of the use of special material in vault construction, from the elementary sheet-iron box one-half inch in thickness to the latest splendid product of the art, consisting of face-hardened Harveyized plates from 5 to 16 inches in thickness, so securely dovetailed and locked together as to render the construction proof against any conceivable method of attack.

By the courtesy of Mr. W. H. Hollar, president of the Hollar Company, engineers and superintendents of bank vault construction, we were recently given an opportunity to inspect the massive safe deposit vaults designed by that company for the Provident Life and Trust Company, of Philadelphia, Pa., which form one of the subjects of our front-page engraving. This illustration is admirably adapted to our purpose, since it exhibits the two latest steps in the development of the high-class treasury and safe deposit vault, the lower vault being of the laminated, or five-ply, built-up type, and the upper vault representing the latest armor-plate construction.

The prototype of the present highly-developed safety vault is to be found in the old strong box, built of oak, clamped with iron, and provided with massive hasp and lock, of which not a few may be found to-day still standing in the ancient cathedrals and municipal buildings of Europe, where, centuries ago, they were doing useful service. It was a natural step from the iron-bound, wooden chest to the iron box, and from that to the all-iron vault half an inch in thickness, which, a century ago, represented the best that our forefathers could produce in the art of vault construction. A structure of this kind, secured by the simple contrivance of a large hasp and padlock, was easy prey to the burglar; and although as time went on the thickness was gradually increased, and the workmanship at the joints improved, the vault breaker continued to have the best of the struggle against the vault designer and maker, and the latter had to face the alternative either of making some radical change in his materials and methods of construction, or of admitting himself beaten in the struggle.

The next answer made by the vault maker to the burglar was the introduction of steel in place of iron, and the fabrication of the steel so that its high qualities of hardness and toughness should both be offered to the best advantage in resisting the improved tools and appliances of the safe breaker. The great requisites in a vault are toughness to withstand stripping, impact, or hammering effects, and intense hardness to resist attack by the drill. And just here the vault makers found themselves confronted by the same conditions as the armor-plate makers. The latter had to provide a plate that was hard enough to resist the attack of the intensely hard steel projectiles, and that still possessed sufficient toughness to prevent it from being cracked or entirely shattered by the impact. The armor-plate makers of twenty years ago solved, or tried to solve, the problem by taking a soft-steel body and rolling down upon it, at a welding heat, a face, several inches thick, of high-carbon steel, the idea being that the hard face would resist penetration and smash up the projectile, while the softer body would hold the hard face up to its work.

The vault manufacturer, on the other hand, met the attack of the drill and the dynamite charge by producing what is known as the five-ply welded plate, which consists of five welded layers, three of which are mild or tough steel, and the two others of extremely hard chrome steel. The two outer layers are of tough steel, the two next layers are of hard steel, and the center is a somewhat thicker layer of tough steel. It is made as follows: The plates of tough steel are raised to a welding heat, and high-chrome steel, in a molten condition, is run in between them. The whole plate is then rolled down to the desired thickness, which will vary from ⅜ inch to 2 inches, as desired by the manufacturer.

With the production of the five-ply plate the vault makers were in a position, for the first time, to offer a structure that was honestly entitled to be called "burglar proof" against the methods of attack which were common at the time of its production. It was tough to resist the impact and shock of high explosives, and its hard-steel layers were sufficient to break the best steel drills of the burglar. But inasmuch as it was necessary, in order to secure the best results from the five-ply plate, to roll it down to comparatively thin sizes, it became imperative to devise some method of building up the walls of a vault to the desired thickness by the use of several of these plates, and of fastening the plates each to the other and bending and securing them together at the joints, which would be proof against attack. Each layer is fastened to the one outside of it by heavy countersunk tap screws, which are tapped into the adjoining plate. In this method of construction the screws, which are, of course, all put in from the inside, are arranged to break joint, as it were, as are also the various horizontal and vertical layers of plates. The result is that the final vault wall, as built up, has the nearest approach attainable to a homogeneous strength throughout, and is thus brought as near as possible to the ideal conditions presented by the single solid Harveyized plate. The whole of the work, as thus assembled, both in the walls and in the angles, is fastened together with heavy tap screws from the inside, and it follows, therefore, that the maximum strength of the construction consists in the aggregate strength



Front View of Hollar's Quadruple-Movement Electrical-Winding Time-Lock.



Section Through Door and Corner of a Laminated Five-Ply Vault.



Model Showing the Method of Jointing the Armor-plate Walls at the Corners.

ARMOR PLATE--THE LAST ANSWER OF THE BANKER TO THE BURGLAR.

of the screws securing the several layers of metal together, and not in the mass of metal itself.

The five-ply type of vault has had a most successful career, and has been built in all sizes, from the small vaults of the country bank up to the imposing structure shown on our front-page engraving. Of the two vaults there represented, the upper one is of the latest armor-plate type, and was built by the Bethlehem Steel Company, and the lower one is of the built-up "standard" type, of Brooklyn chrome steel, and was built by the L. H. Miller Safe and Iron Works. The latter vault is 20 feet square by 9 feet in height; its walls are 6 inches in thickness, while its massive doors are 12 inches in thickness. It represents the highest development of the built-up or "standard" vault; and until the introduction of the armor-plate vault, it furnished the best answer that the banks and the trust companies could make to the tools and explosives of the professional cracksman.

It will be evident that the ideal method of construction would be to employ a single plate which combined the necessary hardness, toughness, and thickness all in one, and so do away, at a stroke, with the weakness which is inherent in the built-up construction.

Now these qualities are all combined in the Harveyized armor plate of solid thickness, which is so tough that it cannot be cracked through, so hard that a flake from its carbonized surface will scratch glass like a diamond, and which may be made as much as 24 inches in thickness without impairing any of its other desirable qualities. The introduction of Harveyized armor into vault construction from designs by the Hollar Company, engineers, may fairly be described as the most important single step ever taken in the development of burglar-proof vaults. A vault built of armor plate, with its joints dovetailed together and keyed from the inside of the vault, and provided with a circular door ground into the armor-plate front, is proof against any known method of burglar attack.

It is not necessary for the Scientific American to describe the manufacture of Harveyized armor plate. It is sufficient to say that after the plate has been cast and forged to the necessary thickness, it is covered with a coat of carbonaceous material and heated for several weeks in a furnace until the carbon, which is the hardening element in steel, has eaten down several inches into the body of the plate. The plate is then reduced to size, and the edges where they lock into each other are machined and ground down to the dovetail shapes shown in our engravings representing the system of joining at the corners or angles. After these joints have been machined and ground to an exact fit, the plates are heated and then hardened by subjecting them to a bath of cold water, which is sprayed upon the plates with great force from large mains 12 inches in diameter. The vaults are built with the hardened surface on the outside. The dovetails are formed with one face square and the opposite face cut at the designed angle. The clearances are so arranged that the dovetails slide snugly into place as the plates are drawn together, and after they have been brought home, long wedging strips and key pieces are driven into place from the inside of the vault, locking the plates securely in position. The joint as thus formed is so close and massive that it is proof against any attack by floating nitroglycerine in from the outside, and wedges will make absolutely no impression upon it, the hard face splintering the wedges just as it does the hard point of a projectile. For the same reason the drill is useless; and as for the method of attack by using the arc light and taking the temper out of the steel, it is sufficient to say that the conditions necessary for the use of the arc are so difficult to obtain, that no burglar could hope to use it without detection. The banking public need lose no sleep over the electric arc scare, of which we recently heard so much.

The introduction of armor plate made it possible to use, with the best results, the round or circular door with all the great advantages that it confers. The door itself and its seating in the front plate of the vault are machined to the exact size, and the two are then ground to a perfect fit, in much the same way in which a gas engine valve is seated. The resulting fit is so close that it is not possible to float the most volatile liquid in at the joint, and therefore this favorite point of attack of the cracksman is now perfectly safeguarded.

The armor-plate vault shown in our engraving measures 23 feet by 20½ feet, and is 10 feet in height. It is built of Harveyized nickel-steel armor plates weighing 200 tons. The entrance to the vault is through one of these plates, which is 12½ inches in thickness. The circular door for this entrance is 7 feet 7½ inches in diameter and 13 inches thick, and weighs complete over 16 tons. The hinge is so delicately hung on roller bearings that a child can easily swing the door to and fro. A small round emergency door has been provided in the rear of the vault for ventilation, as well as to guard against the possibility of lock-out through the failure of any of the delicate and intricate time-lock mechanism to operate.

The hinge, compressor, and bolting mechanism was made by the Herring-Hall-Marvin Safe Company. The latter consists of twenty-four 3½-inch diameter cold-rolled steel bolts, which are arranged to slide in and out radially from the center of the door. These locking bolts are moved by a double reserve Yale automatic; this mechanism is in turn checked and controlled by a four-movement electrically-rewinding time lock, which was also manufactured by the Yale Company.

The act of closing the door releases the automatic mechanism which carries the locking bolts into the locked position, and they are retained in this position until the expiration of a predetermined time, when the time lock releases the automatic, which in turn withdraws the bolts, after which the doors may be readily opened. It should be borne in mind that all of the foregoing operations take place without any connection through the doors.

Should conditions arise, however, which would, in the opinion of the proper custodians of the vault, justify them in keeping the vault locked for any additional number of hours, beyond the time for which it was originally set, this can be accomplished without opening the vault doors, and without anyone having access to the locks. The value of this feature may be illustrated when the contingency of fire or riot is considered, for in either case it would be undesirable to permit the action of the timelock mechanism to make possible the unlocking of the vault. Under these conditions, all that would be necessary would be to simply close an electric switch, when the time-lock movements would be electrically rewound, thereby preventing the opening of the doors until the expiration of the added number of hours. Both the Carnegie and Bethlehem Steel Companies are now engaged in the construction of very large vaults of Harveyized nickel-steel armor plate.

AN IMPROVED FORM OF AUTOMATIC CARBURETER.

The annexed longitudinal section shows the interior arrangement of a new automatic carbureter for gasoline engines. The main air pipe is located vertically in the center of the float chamber, and in its center is placed the spraying nozzle with adjustable needle valve, as shown. Surrounding the needle valve is a special, dome-shaped, coiled spring which provides a small opening for the main air supply, and hence produces a strong suction at the nozzle tip when the engine is being started or run at a slow speed. As the throttle valve is opened and the engine speed and suction are increased, the coils of the spring are separated by the augmented suction, thus allowing much of the air to pass directly upward through the coils at the curved or inclined part of the spring. This prevents an increase in the suction at the nozzle tip, which would occur if a larger quantity of air were drawn in a given time through the small opening around the tip, as is the case with most carbureters. Instead of providing suction-operated auxiliary air valves for the purpose of subsequently admitting more air to dilute the richer gas thus obtained at high speeds, Mr. Charles T. Gaither, inventor of the carbureter shown, has carried out the idea of keeping the suction constant at the nozzle, and thus of always maintaining the same mixture, by means of the ingenious arrangement shown. In the carbureter, as at present manufactured, the spring is about 2 inches in diameter at the base, narrowed to ½ inch at the top. It is made of 1-16-inch steel wire, copper-plated to prevent rusting. On account of the large diameter of the spring, a slight spreading of the coils will allow a very considerable quantity of air to pass between them. It may happen that the needle valve must be opened so much, in order to supply sufficient fuel for full power at high speed, that too much gasoline is drawn at low speed. This can be regulated by opening the auxiliary air inlet the right amount, or until a perfect mixture is obtained at low speed. Thus there are two adjustments, the needle valve and the auxiliary air intake, for accommodating the mixture to the compensating spring. The auxiliary air intake, also, is made up of a dome-shaped coiled spring, the coils of which are separated enough to let pass the requisite auxiliary air by simply unscrewing a stud set in the wall of the vertical main air pipe. This pipe is surrounded by a cork float pivoted upon a vertically-adjustable pin in the wall of the carbureter, by means of which it is possible to set the float so that it will close the conical supply valve at any desired point and thus maintain the fuel level nearer or farther away from the tip of the spraying nozzle. This is an adjustment that is not absolutely necessary, but which nevertheless is sometimes found useful.



SECTION OF A NOVEL AUTOMATIC CARBURETER.

The ordinary form of automatic carbureter, of which the Krebs (illustrated in our February 14, 1903, issue) was the prototype, has some form of auxiliary air valve placed between the spraying nozzle and the inlet pipe of the motor in about the position of the auxiliary air intake shown in the cut. As the suction increases, this auxiliary air valve is opened, thus tending to diminish the suction past the spraying nozzle, so that it remains nearly constant and, at the same time, to dilute the relatively rich mixture that may be at first obtained when the throttle is suddenly opened.

An appreciable period of time is taken for the mixture to become correct again, if, when the motor is running throttled, the throttle valve is suddenly thrown wide open. The result is that with most of the automatic carbureters there is an appreciable lag before the motor responds. With the Gaither carbureter, however, this lag is practically *nil*, and the motor seems to respond instantly when the throttle is opened. The reason for this is doubtless the location of the suction-controlling device at the spraying nozzle, so that the mixture is maintained uniform as it is formed.

Starting of the motor is easily effected with this carbureter, as several fine holes on the inclined sides of the tip spray gasoline upon the inside of the coiled spring when the carbureter is primed, and the fuel, trickling down over the corrugated surface, is readily drawn by the inrushing air when the motor aspires.

A Wonderful Lock.

Mr. Neuman Tobias, of Kingston, Jamaica, has invented a most remarkable lock. The combination consists of four sets of 24 letters of the alphabet, which can be set to a sentence in most modern languages. When one letter is used in one alphabet and another in the second set, and so on, it becomes a very complicated matter indeed. Then there is the initial problem of what language it has been keyed in, to be solved by the man who attempts to open the safe. Furthermore, instead of letters, Mr. Tobias has employed four sets of numerals. Assuming that the lock is set to a figure in the number of 3,030,303,030,303,030, it would take anyone who undertook the job of unlocking the safe 96,090,278 years, 269 days, 30 minutes, and 30 seconds working at the rate of 60 numbers a minute to arrive at the proper "combination." During this time he would have no time for eating, drinking, or sleeping.

The Current Supplement.

The current Supplement, No. 1581, is begun by Enos Brown with an article on a new type of bascule bridge which has been erected in San Francisco. Concrete Aggregates is a subject which Mr. Sanford E. Thompson discusses from the practical standpoint. James P. Maginnis continues his monograph on reservoir, fountain, and stylographic pens. Practical methods of waterproofing and fireproofing are given. Julius Wile writes on gas producers for power, and gives some telling arguments why producer gas should be used for certain purposes. Lightning and the electricity of the air will be discussed in a series of articles by Alexander G. McAdie. The first of these articles appears in the current Supplement. Louis A. Fischer concludes his history of the standard weights and measures of the United States.

The celebration of the first settlement of America at Jamestown will take place in 1907. The navies of the United States and foreign countries will be in Hampton Roads, and representatives of the armies will assemble upon the adjoining land near Fortress Monroe, Va. At the same time, in connection with the State of Virginia, the city of Norfolk, assisted by the different States of the Union, will hold a great historical and industrial exposition along new lines, out of the beaten track of previous expositions. A striking new feature that seems to be of more than ordinary interest to our readers is the proposed erection of a special building to be known as the Hall of Modern Inventions.

Correspondence.

A Mercury Photometer.

To the Editor of the SCIENTIFIC AMERICAN:

I have been very much interested in the articles published in your journal on standards of light and standard photometers. Several years ago I conceived the idea of such an instrument, which I called a mercury photometer, and which was made in a manner not unlike the ordinary thermometer, using, however, an electric circuit and a selenium cell. The following is a detailed description of this instrument:

It is necessary to provide a frame similar to the ordinary thermometer frame, but deep enough at the back to receive a small dry battery, and having room at the top for a selenium cell. The battery is connected to the selenium cell, and in front of the latter is placed a finely-ground glass plate, to diffuse the light evenly and to protect the cell from undue excitation. The cells are connected by a filament or a thin platinum wire, which passes through the mercury bulb of the thermometer column, and thus the temperature of this filament affects the expansion of the mercury and, consequently, the height of the mercury column in the thermometer. The filament might be covered with a very thin sheet of asbestos, just sufficiently thick to insulate it from the mercury, and with this covering is fused into the mercury bulb. The current strength would be governed by the selenium cell, and would be proportionate to the amount of light falling upon the latter through the ground glass. Thus the height of the column of mercury, in accordance with the amount of heat given off by the platinum filament, which in turn is proportional to the amount of light falling on the selenium cell, would be in direct proportion with this degree of light.

To allow for the rise of the mercury due to the local temperature conditions, a sliding scale might be provided alongside the tube, which could be used in the following manner: Suppose the local temperature to be 70 degrees. This temperature is noted, and the zero point of the sliding photometer scale is placed at this point of an ordinary Fahrenheit scale, with which the frame is also provided, then the units of light may be read directly from this sliding scale between the point 70 on the Fahrenheit scale and the top of the mercury column. If the ground glass is covered and no light is admitted to the selenium cell, the mercury column will merely register the ordinary temperature, and thus, if a cover be provided to exclude the light from the glass, the temperature can be determined by keeping this cover closed. Besides this a switch could be provided for throwing the current in or out to answer the same purpose.

The upper limit of the rising of the mercury column would have to be in the neighborhood of 600 deg. F., as the point of vaporization of quicksilver is about 662 deg. The photometer scale should be divided into 100 parts, starting from zero or absolute darkness. Various lights, such as a good reading light, light too bright for the eyes, etc., could be indicated on this scale, and thus the instrument would become invaluable in the school room. JOSEPH BREVAR.

Cleveland, O., March 10, 1906.

An Object Lesson in Aeronautics.

To the Editor of the SCIENTIFIC AMERICAN:

The fate of Paul Nocquet, who made an ascension with a coal-gas balloon Tuesday evening, April 3, 1906, from 135th Street, New York, landed about 10 o'clock the same evening near the life-saving station at Jones's Beach, Long Island, and then wandered two miles away through a swamp to his death by cold and exhaustion at Cott's Island in Bass Creek, is a valuable and instructive example of things one ought not to do.

Daring is not a prerequisite in ballooning or automobiling, and recklessness is homicidal in any walk of life. Paul Nocquet's first imprudence was a night ascension at an inclement season of the year, no more suitable for ballooning than is a sloppy spring road in the country for automobiling. His final mistake, after wandering in darkness and space above, consisted in leaving the safe location of his landed balloon and wandering in darkness and space below. The risk on earth seems greater than above, though both could have been avoided by an earlier trip by day. Surely the fate of Paul Nocquet is not an example of the inherent dangers of air journeying.

I take some credit to myself for having indulged in this pastime during thirty summers without harm to myself, and for having managed thousands of hydrogen-gas balloon and airship ascents by other persons, aeronauts, and the unskilled public, without harm to any. This large experience must have a certain value in the critical diagnosis of the symptoms of the present ballooning epidemic.

I have steadfastly disapproved of motiveless night ascensions at inclement seasons.

Prof. Wise, the veteran survivor of 1,200 gas-balloon voyages, and the pioneer long-distance aeronaut who traveled 1,200 miles in 19 hours forty-five years ago, finally lost his life on a stormy night in company with young Burr, a St. Louis banker, who wanted a night ascension. They probably met their fate in a Michigan swamp or a Canadian wilderness that night.

Aeronaut Donaldson with Reporter Grimwood met death through similar causes, starting from Chicago in a storm across Lake Michigan which wrecked forty vessels that night. After this a long interval elapsed without any fatality with coal-gas balloons in America. There has never been a fatality during any hydrogen-gas balloon ascension throughout America.

Compared with any other means of transportation, the aerial line seems miraculously safe. Yet there is no magic in it. One should have good weather, good apparatus, good gas, and good common sense, both in the air and on landing. Among all ascensions under my charge, the rule of sticking to the vessel was only broken once, by a reformed hot-air balloonist, who made a first hydrogen-gas ascension with my balloon, and on landing, let it fly. I traced this balloon from Willimantic, Ct., to the Atlantic coast, where it took a trip over sea, and returned next day, and was recovered in perfect condition near Newport, R. I. This led to my investigating sea breezes, which blew low toward the land, and generally seaward higher up. As a result of this, various balloon flights were made from the Atlantic coast, returning safely to land by the lower current. It is perfectly in line with this experience that the Nocquet balloon should float over sea on the higher current, and draw inland with the lower, landward wind.

I have some curiosity now to learn if the tide was also flowing inland when the Nocquet balloon came ashore. No scientific records exist of night voyages in cold weather on our coast. I strongly disapprove of such attempts. Neither can I see pleasure in them. They have no excuse as "sport."

The record of cold-weather ballooning began this year with an ascent from West Point, a 40-mile trip, amid winter rigors, to a landing in darkness, facing unknown dangers. Next an ascent from Tuxedo, late, with poor gas, no ballast, and a brief rise and fall. Following this was an attempted balloon race from Pittsfield, Mass., resulting in the destruction of one balloon and the escape of the other in the fierce March winds. Next the 20-minute flight of Count de la Vaulx, ending with a skillful beach landing. Next the adventurous death of Paul Nocquet.

What a record is this to repress ambitious aspirations to ride the wind! I earnestly protest that this is neither science nor sport. It is simply inopportune haste to "rush the season." "Wait till the clouds roll by," and balmy airs and sunny skies invite a visit and a pleasant loiter along the heights where "distance lends enchantment to the view," which literally "beggars description." Then harness up your balloon car, and start early from some safe inland point, whence you may sail all day and picnic in midair. This is ballooning, and I will stake my reputation on its success and safety. CARL E. MYERS.

Balloon Farm, Frankfort, N. Y.

A Strange Cargo.

One of the strangest cargoes a vessel could possibly have was unloaded at the London docks toward the close of March. It consisted of several sacks filled with dried flies, consigned to a large firm of grain merchants. These flies, originating in Brazil, have been purchased for use in the manufacture of food for chickens, cage birds, and the like. They were caught on the river Amazon by Brazilians, who travel up the river in flatbottomed boats, and who are provided with gauze nets, with which they capture these insects in millions, as flies hover in dense clouds over many of the swampy reaches of the Amazon.

The flies thus caught are killed, dried in the sun, and then placed in sacks. Upon arrival in London they are mixed with millet and other grain, and are sold as chicken food, etc. Some time ago the Brazilian government, fearing that the fish in the Amazon River would be starved, forbade the exportation of flies; hence the price of this strange commodity, which used to be 6d. per pound, has now risen to 1s. 6d. per pound, and often a little more.

Constitution and Properties of Aluminium Steels.

Aluminium steels have been studied by M. Osmond and M. Hadfield. M. Hadfield has shown that the malleability ceases at about 5.6 per cent of aluminium, and that the elongations commence to lower at 1.5 per cent. M. Osmond has shown that steels containing 5 per cent of aluminium no longer present the point of transformation A_3.

Resuming the study of these alloys by the same method as that employed for other special ternary steels, M. Guillet has been able to establish the constitution of these alloys and the bond which unites their mechanical properties. These experiments are said to show that aluminium has no important action on the mechanical properties of steel so long as quantity is less than 2 per cent. Up to 15 per cent aluminium is dissolved in iron. The ferro-aluminium solution thus formed does not dissolve carbon; so perlite takes a granular form, which explains the fragility of certain steels; martensite is produced by tempering only where there is no perlite. Finally, free martensite is found in steels with high percentage of aluminium, although these steels contain less than 0.850 per cent of carbon.

The Maternal Love of Spiders.

It is not unusual to find, in fields of oats, panicles which are more or less enveloped in spiders' threads crossing in every direction, so as to form whitish nodules the size of pigeons' eggs, and inclosing in their tissue the spikelets, and sometimes the leaves of the grain. These are the nests of a spider, the *Chiracanthium carnifex*, which is of a yellowish gray color with a brownish band on the dorsal face of the abdomen.

Upon opening one of these nests, it is seen that the interior is hollow and that only a small part of the cavity is occupied by the eggs and the mother. The former are in a little spherical cocoon, formed of silk like the side of the nest to which it is securely attached, while the female which has laid the eggs remains within the nest; she is often found resting on the cocoon itself, but sometimes leaves that place. When an opening is made in the wall, she goes to see what has happened, and may even go outside, but she hastens back, and immediately begins to weave a tissue to mend the breach in the nest. Her love for the cocoon is manifest, for she never abandons it even when tormented.

How far-reaching this maternal love is, and its duration, is the question which Mons. A. Lecaillon has attempted to solve by removing the true mother of each nest and giving her place to a stranger, which we shall call the "pseudo-mother." Some of his experiments have all the interest of a little drama.

After having made a break in the web of the nest, the mother is removed and her place is given to a pseudo-mother. She enters it without hesitation, takes a survey of the interior, and at once begins to close the entrance. The mother is then brought to the nest. She goes toward the entrance and wishes to penetrate it, but stops on finding the place occupied. The pseudo-mother, who cannot come out while her adversary remains at the entrance, seeks to defend herself against the attack with which she is threatened, and puts herself on the defensive. The mother then shows signs of violent anger. She rocks her body from right to left and from left to right, and the two spiders exchange blows through the opening.

The mother's attitude is violently offensive, menacing to seize her adversary, while that of the pseudo-mother—who cannot come out to save herself, since the opening is besieged—is one of fear and only defensive; she is conscious that she is not at home. Twice the besieger leaves the entrance to find some other place to penetrate into the nest. Her opponent then attempts each time to jump across the opening to save herself, but the mother, seeing this, immediately returns to seize her. The pseudo-mother, not entirely out of the nest, has only time to throw herself back, and finally, the mother having withdrawn the third time, she is enabled by a quick movement to escape, although the former again advances, but cannot seize her.

The attack of the nest by the mother continues a quarter of an hour. Then, after having spent several seconds in assuring herself that her rival has disappeared, she enters, but comes out two successive times in order to again explore the exterior. Finally she returns and, after remaining immovable for five minutes, begins to stop up the aperture. The pseudo-mother is placed upon the nest three times, but refuses positively to approach from the side, and retreats precipitately.

This experiment shows that the pseudo-mother readily adopts another nest, even when she has been separated from her own several days, but does not defend it against the attack of the mother. When the latter is in the nest, she refuses to try to enter. The mother, on the contrary, does not hesitate to besiege her enemy until she overpowers her and regains possession of the nest.

The experiment is repeated after the mother has been kept from her nest twenty-four hours, and it has been found that she shows great attachment to it, with a desire to again gain possession. But, at the same time, the pseudo-mother has become attached to her nest of adoption, not leaving it voluntarily, and even defending it vigorously from the attack of the true mother.

When the mother had been kept from the nest eight days, she did not show any interest in her eggs, nor try to recover them when placed in the vicinity.

Maternal love among the spiders which have been studied is therefore very manifest, but it diminishes when the mother is kept away, and finally disappears. How similar are human sentiments under like conditions!—Translated from La Nature.

THE OVERFLOW OF THE COLORADO RIVER AND THE SALTON SEA.—II.

BY GEORGE WHARTON JAMES.

In last week's SCIENTIFIC AMERICAN it was briefly shown what efforts had been made to close the "temporary expedient" cut of the Colorado bank below Yuma at the point known as the third or lower intake.



Diagrams Showing Location of Intakes.

The accompanying diagram will give the location of the intakes. Intake No. 1 is where the old headgate was placed, which soon became choked up with detritus and was used only during high water, as at low water it was some four or five feet below water level. Intake No. 2 was cut on the Mexican side of the boundary, to conform with a provision of the Mexican charter to the irrigation company. It was practically unused. Intake No. 3 is the "temporary cut" which has caused all the trouble, and which was made because it was cheaper than dredging out intake No. 1. It was the intention of Chief Engineer Rockwood, when this cut was made, to place therein, as speedily as funds would allow, the necessary headgate required, so that this would have become the permanent intake, properly under control, required by the Mexican concession. It was also his intention, constantly expressed, to construct a permanent and sufficient headgate at or near intake No. 1; and, as will be seen shortly, these two are the major propositions upon which the company is now vigorously working.

When work on closing up Intake No. 3 began in May, 1905, the cut was about 100 feet in width. When the water subsided it had grown to 800 feet in width, and was still carrying about 14,000 cubic feet of water per second, with a depth at one point of 24 feet.

On July 18 the Yuma gage showed 121.8 feet, with 18,000 cubic feet flowing through the intake, and only 7,000 passing down the old river channel to the Gulf.

A new attempt was now to be made to control the water. A site was chosen a mile above the former one. By reference to the diagram, it will be seen that an island divides the Colorado River channel opposite intake 3. This island is about 3,000 feet long by 1,200 feet wide. The plan now proposed was to construct a light jetty of piling and brush, beginning at a point on the Mexican side marked *A*, and continuing to a point on this island marked *B*. The idea in this effort was to control the river by the formation of a sand bar behind the brush, thereby diverting the main portion of the flow to the Arizona or eastern channel of the island. The experiment failed. In the meantime preparations were under way for a more ambitious undertaking. In August materials were ordered for the new attempt. This involved the construction of a gate at intake 3 large enough to pass the entire flow of the river at low stage, after building which it was the intention to construct a permanent dam across the rapidly widening "cut." When this dam was secure the gate would have been closed, thus raising the water and throwing it down the old channel. This gate it was proposed to make the one required by the Mexican government. The floor was to be of concrete three feet in thickness on a pile foundation. The superstructure was to be of wood temporarily, but ultimately to be replaced by concrete.

A two-yard dipper dredge was at once set to work excavating a big channel to carry the water around the gate site, as marked *E* on diagram 2, and the steamer ran around this pass while work on the dam progressed. This consisted of piles driven at the point marked 5 on Diagram 2. These were taken completely across the channel, capped, and a runway built on them from one side to the other. The steamer hauled gravel for a week to make a bottom around the piling, and the cutting of 150 tons of brush for the fascines was rapidly proceeding. All the material was on the ground for the new structure, and it seemed on a fair way to be successful, when orders came from headquarters to stop the work. The water was rising so rapidly at Salton that some other expedient must be tried at once requiring less time, and thereby saving the complete washing away of the railway tracks.

The Southern Pacific engineers proposed the construction of a pile dam across the west channel, near the head of the island at the point marked 6 on Diagram 2 in order to force the water down the east channel. The west channel was here 650 feet wide and about 10 feet in maximum depth. A dam was to be built of woven wire cable mats, filled in with bundles of brush and barbed wire anchored in the river with piling. When completed it would have to withstand a water pressure of 16 feet. Work was begun in the middle of the channel, and with two pile-drivers and a large force of men rushed as much as possible. All progressed favorably until the piling and mats reached within a hundred feet of the shore on both sides. As the work was nearing completion water was raised in the old river channel on the west side fully 14 inches. No matter how much weight was put on the mats to prevent scouring, the water would get under them and cut away the channel. The island, on which all hopes depended, began to wash away. On the 29th of November the severest flood since February, 1891, swept down the river with resistless force, and carried away a portion of the work and much of the equipment. The island was completely flooded, and 240 workmen, 13 wagons, a carload of hay, another of provisions, and 38 head of horses had to be transferred to a barge instanter, or they, too, would have been swept away.

This was the last effort prior to the one upon which work is now progressing. The present plan is to construct a permanent headgate at point marked *M* on Diagram 1. This is four miles up the river from the lower intake, and on the United States side of the boundary. The anchoring foundation is solid rock, and the structure is to be of reinforced concrete. It will be 185 feet wide and 26 feet high above the sill. The floor is to be placed 11 feet below the low-water mark and 4 feet below the river's bed. It will have 154 feet of water openings, and at the lowest water stage of the river can pass 7,000 cubic feet per second.

It will be composed of twelve reinforced concrete cells about 16 feet wide by 14 feet high. These will be filled with rock, gravel, and sand, which will be fully ample to make the structure stable, so that it will withstand the pressure of the heavy floods.

On March 20 the excavations were all completed, and the concrete work actually begun. This gate will carry 7,000 feet of water per second, while the flow of the Colorado at low water is only about 5,000 feet, and sometimes as low as 3,500 feet per second. The building of this gate implies the widening and deepening of the old canal, which is but 80 feet wide, and at low water can carry but two feet in depth. This is to be enlarged to 170 feet wide and 11 feet deep (see dotted line *N*, Diagram 1.) below low water. This work involves the excavation of 1,800,000 yards of earth.

The permanent work at intake 3 is resumed near the point where it was abandoned last year (Diagram 1, *P*) with the necessary enlargements and alterations caused by the changes brought about in the interval by the power of the stream. From 300 feet in width it has grown to over 650 feet. (See dotted line in Diagram 1, marked *R R*). The floor of the new gate will be 200 feet wide and 60 feet long. It will be placed 11 feet below the extreme low-water level in a quicksand formation, and anchored to 533 foundation piles. Aprons 30 feet in length extend from the floor



Cofferdam at the Site of Headgate No. 2.



The Site of the New Concrete Headgate No. 1 at Hanlon's on the California Side of the Boundary.



One Year's Growth of Willows in the Silted-up Canal Bed, Showing the Fertility of the Soil.

THE OVERFLOW OF THE COLORADO RIVER AND THE SALTON SEA.—II.

to the coffer-dam wall, and wings 100 feet in length extend up and down the stream. Nearly 600,000 feet of lumber, including 1,680 lineal feet of sheet piling wall, 6 inches thick, driven from 12 to 22 feet, will be used in its construction and protective works. Eight hundred and fifteen round piles will be used in the foundations, wings, and diversion jetty.

Levee Built Parallel with the South Branch of the Alamo River Near Headgate No. 2 to Stem the High Water.



Two-Yard Dipper Dredge at Work at Headgate No. 2.

The earthwork in the approaches to the gate involves the moving of 120,000 cubic yards of earth in excavation an average distance of 350 feet, and the fill in the diversion dam and levees contains 59,600 cubic yards of earth, 2,000 cubic yards of brush, and 20,000 grain sacks filled with gravel.

It was decided on the 17th of December, 1905, to resume this work. New material had to be ordered, as all the original supply had been removed to carry on the work which the November flood had destroyed. On the 8th of January, 1906, work on the walls of the coffer-dam began. This is 250 x 120 feet, and contains 740 sheet piles 6 x 12 inches, 22 feet long. It was completed and the earth within excavated on the 15th of February. An 8-inch and a 6-inch centrifugal pump were set to work, and lowered the water as far as was necessary in two days' time. The 8-inch pump now keeps it at a proper level. A force of 160 men is at work here now, day and night. As soon as water can be turned into this gate, a permanent dam will be constructed across the channel slightly below the point marked 5 on Diagram 2.

It should not be forgotten that fifty miles away from the Colorado the engineers are battling with another problem caused by the overflow. At Sharp's, seven miles southeast of Calexico, is the point of diversion, where the water from the main canal (which, it should be remembered, is the bed of the old river Alamo, dry except in time of flood) is taken, and by means of canals, all of which are controlled by headgates, is supplied to the various sections of the Imperial country. When the flood began to pour down the Alamo, the result was to scour out and deepen the channels around the heading at Sharp's. This scouring still continues, and will continue, so long as the flood is allowed free course.

All That's Left of Salton.



The Salton Salt Works Now Under Water.

The old waste headgate was found insufficient for flood purposes, and a new and large structure was erected. But the unusual flow began to undermine the new gate by the cutting back of the channel under the fall. It was necessary therefore to close this gate to save it, and construct an apron to protect the channel below the fall, and, therefore, the abandoned headgate had to be put into commission again. An emergency chute was attached to it in February, 1906, with a flume 28 feet wide and 6 feet deep, and through which 1,300 cubic feet of water is flowing to waste every second. This waste flow is rapidly cutting down the channel to the depth already of some 18 to 20 feet.

Work on the apron on the new waste gate is rapidly progressing, however, when water will be turned therein, the old gate closed, and a restraining jetty built across the old channel, so that the full flow will be under complete control.

Of the Salton Sea it can now definitely be said that its new life will not be long. Not that it will entirely disappear. This is scarcely to be expected. The seepage and drainage from so large an area as the Imperial Valley under irrigation will necessarily be large. This will undoubtedly keep the sea at a certain level. What that will be has not yet been, and scarcely can be determined, though it is certain it must be several feet, probably many, below the present level.

Switzerland is likely to furnish a supply of asbestos for the trade, if we are to believe the most recent reports, which state that important layers of asbestos have been recently found in the Puschlav Valley, which is located in the Canton of Grisons. A syndicate has been formed already in order to work these deposits. At the same time the syndicate proposes to construct a line of electric road which will connect the mine with the railroad station of Tirano and thus give a quick means of transporting the material. One of the principal Swiss firms which are interested in the enterprise is the house of Victor Schneider, of Geneva.



A Reminder of the Ruined Salt Industry.

Pile Dam Built Partially Across the Colorado to Force the Water Down the Silted-up Canal.

THE OVERFLOW OF THE COLORADO RIVER AND THE SALTON SEA.—II.

VESUVIUS: PAST AND PRESENT.

Because of its constantly recurring outbursts, Vesuvius has been more carefully watched than perhaps any other of the world's volcanoes. Delicate instruments have been devised to foretell an eruption, and it is no doubt due to these that the crater's present activity has cost only hundreds and not thousands of lives. And yet we can no more account for the slumber of Vesuvius than for its violent outbursts. Even constant observation has not always enabled science to forecast the occurrence of the upheavals. During the great eruption of 1872, Prof. Palmieri's delicate seismographic instruments at the Monte di Somma observatory gave not even the slightest indication of what was to come; and so while we are familiar with the record of the past, that of the future is often veiled.

Although there were vague legends among the ancients concerning the fiery nature of the mountain, it was not till the year 79 that the true character of the great solitary cone rising from the plain of Campania was suspected, notwithstanding that sixteen years previous, in 63, and repeatedly thereafter, severe earthquakes partially destroyed the cities in the vicinity of the Bay of Naples. From the geographer Strabo we learn that the slopes of Vesuvius were at that time covered with fertile meadows, though the summit, which was flat and apparently without traces of a crater, was sterile and showed indications of a fiery origin. Almost without warning on August 24, 79, an enormous cloud of black vapor rose from the summit accompanied by the explosion which shattered the top and marked the beginning of the great historic eruption so ably described in the letters written to Tacitus by Pliny the younger, nephew of the famous Roman admiral of that name, who perished while hastening to the relief of the inhabitants of Pompeii, Herculaneum, and Stabiæ with the fleet under his command. Pompeii was overwhelmed and buried to a depth of many feet by a terrific rain of volcanic ashes. We can only estimate the number of the inhabitants who perished, but the mode of death is indelibly recorded in the molds of bodies found in the ashes of the dead city by the excavators of to-day. Herculaneum, on the other hand, was destroyed, not by a great flow of lava, as is commonly believed, but by torrents of boiling mud formed in the air by the condensation of great masses of vapor laden with lapilli or scoriæ, as the volcanic sand or ashes are known.

The first eruption definitely recorded after this was described by Dion Cassius. It occurred in 203, and appears to have been one of extraordinary violence. In 472 the mountain burst forth again in a terrible upheaval, during which it was said that clouds of ashes were carried as far as Constantinople. In the period between the first outburst and the year 1500 nine eruptions of greater or less intensity were recorded, while between 1500 and 1631 Vesuvius was entirely quiescent. So deep was the mountain's slumber during this time that it again became covered with vegetation and cattle peacefully grazed in the crater. Strangely enough, during this period Etna labored ceaselessly, and Monte Nuova was formed by an eruption near Pozzuoli. The lull was broken by a terrific outburst, the first of which we have a detailed account, on December 16, 1631, when huge clouds of vapor, violent earthquakes, showers of ashes and rocks, and no less than seven great streams of lava overwhelmed five of the neighboring towns, with a loss of thousands of lives, and even spread terror in Naples itself. This tremendous convulsion inscribed its memorials on the slopes of the mountain in obliterated estates and ruined villages. It appears that Vesuvius did not assume its present form until near the end of the seventeenth century, for Sorrentino describes an eruption of 1685, during which there arose "a new mountain within and higher than the old one and visible from Naples." Thus it seems that the present Monte di Somma is really the original Vesuvius, and that the present cone is little more than two centuries old. From May to August, 1707, a continuous series of eruptions involving the loss of some three thousand lives again devastated the vicinity, and in 1737, 1760, and particularly in 1767, Vesuvius repeatedly manifested activity of a terrific nature. In one of the accompanying illustrations is shown a sketch made by Sir William Hamilton before the great eruption of 1767, in which there appear to be three craters, one within the other, the outer of which is Monte di Somma, and the second the present cone of Vesuvius.

A stupendous eruption took place in 1779 during which huge red-hot stones were hurled to a height of over 2,000 feet. The eruption of 1794 was even more terrible in its effects and was remarkable for the vast streams of lava which were precipitated into the sea near Torre del Greco. During the nineteenth century volcanic outbursts of remarkable violence occurred in 1804, 1805, 1822, 1831, 1850, 1855, and 1858. During the last-mentioned the upper crater sank several hundred feet below its former elevation. In 1861 another exceptionally violent outbreak occurred which again devastated Torre del Greco.

After a decade of comparative quiescence the mountain inaugurated a new series of outbursts by the emission of a number of small streams of lava in January, 1871, a series which culminated in 1872 in the tremendous eruption of that year. The greatest intensity was manifested from the 24th to the 30th of April, and during this period great streams of lava burst forth from all sides of the slope. One of these issued with such suddenness at the Atrio del Cavallo—the valley between the cone and Monte di Somma—that it overtook and destroyed a number of persons out of a crowd of spectators. At the same time the crater vomited great masses of vapor, stones, and lava to a height of over 4,000 feet, while clouds of ashes rose double this distance into the air. Such was the violence of this great eruption that it seemed as if the gigantic tragedy of 79 were about to be re-enacted, for several of the great molten rivers even threatened to reach the walls of Naples itself, while the storm of ashes and red-hot stones appeared almost inexhaustible. Until 1895, Vesuvius remained in a fairly quiet condition, but in that year a violent eruption took place, accompanied by a flow of lava which continued to advance for a number of years, but fortunately did not directly threaten any of the neighboring towns or villages.

The present eruption is unquestionably one of the most violent of modern times and already has shown itself to be of a most destructive nature. The flow of lava has not been of remarkable magnitude, though this, too, has caused enormous damage; but the fall of lapilli and stones has been almost unprecedented. The danger due to the latter is the more pressing one, and the great loss of life can be laid at its door alone, for the people, terror-stricken by the violence of the volcanic detonations and the murky yellow gloom, huddle together in buildings, many of which collapse under the weight of the accumulated material which has fallen upon them. Even in Naples itself this danger has been followed by fatal results, for the direction of the wind, not as in former eruptions, has been steadily toward



Sketch of the Crater of Vesuvius by Sir W. Hamilton Prior to the Eruption of 1767.

the crowded city. The darkness which has enshrouded the vicinity for days has been so deep that it was not possible for vessels to enter or leave the harbor, and it has at times raised the terror of the thousands of homeless refugees to a pitch bordering on frenzy. The communities lying on the slopes of the mountain have naturally suffered most severely, and entire towns have been wiped out with heavy loss of life, while miles of fertile, blossoming farms and vineyards have been converted into a desert of smoking gray ashes. Astonishing as it may seem, the seismographic observatory on Monte di Somma again appears to have escaped the general destruction which involved the railway up the mountain and the rest houses. This is probably due to the foresight of the founder, who placed it on a solid rock ridge and in such a situation with regard to the natural courses of the lava streams that its only probable peril arose from the fall of volcanic bombs and ashes. During the eruption of 1872 Prof. Palmieri remained at the observatory the entire time. Toward the end of the convulsion two streams of lava coursed down ravines on each side of the building, and notwithstanding that all the doors and windows were tightly closed, the temperature within rose to 178 degrees, causing the inmates to suffer terribly. Prof. Mattucci, the present director, has also remained at the observatory during the present eruption, and notwithstanding great suffering and the destruction of many of the delicate instruments, has probably succeeded in recording many valuable observations.

It appears that during this eruption great changes have again been wrought in the form of the mountain, and it will probably be found when the crest is once more visible, that as in the great eruption of 79 the major portion of the top has been completely blown away to be rebuilt in succeeding years by the slow welling forth of lava and ashes. After the first great historic outburst, Vesuvius never regained its original appearance, and a remnant of the broken wall of the crater valley which crowned the older summit is still visible in Monte di Somma. During some eruptions the mountain has increased in height and during others it has sunk hundreds of feet. This alternate rising and falling of the top is a portentous feature of the history of Vesuvius and is indicative of the constant state of unrest in which the mountain has labored since the beginning of the Christian era.

That there is nothing within the range of human knowledge which possesses greater power to compel sheer terror—more psychological than physical, perhaps—and abjectly helpless fear in the mind of man than a violent volcanic eruption, is undeniable. But either the exigencies of life or some peculiarly fatuous mental characteristic brings back to the very shadow of the great destructive agency those who fled in panic from their doomed habitations. There is no better example of this curious, careless attitude than the town of Torre del Greco, four and a half miles from the foot of the mountain, which has been overwhelmed no less than seventeen times. Incredible as it may seem, Martinique and St. Vincent, in the West Indies, the scenes of almost unparalleled devastations, which involved the loss of nearly half a hundred thousand lives, are being re-peopled; and doubtless as soon as Vesuvius, metaphorically, droops the lid of its fiery eye once more, we shall see the Italians returning to the ruins of their homes to repair by years of work the destruction caused in as many minutes, and to again populate the scores of little towns and villages, trusting to their numerous patron saints to avert such disasters in the future.

The Need of Medical Men in the Claim Department of Railroads.

According to Dr. Marcus H. Thomas, who points out the importance to the railroads of first aid to the injured, both from a humane and economic standpoint, in the January 6 issue of the Journal of the American Medical Association, the railway accident, in spite of modern inventions and appliances, is not only apparently inevitable, but on the increase. Among the 1,300,000 persons engaged in operating the railroads in the United States, statistics show that one in each 500 was killed during 1904, and one in every 24 was injured. Taking up the consideration of the subject from the standpoint of sordid advantage, "the one which should be of paramount importance to the railroad, with whom the economic question is always one of vital interest," the author says:

"The steam railroads of the United States pay annually in damages to injured persons 0.74 per cent of their gross earnings. This is seemingly a trifling decimal, but in coin and currency it amounts approximately to $14,000,000. In addition to this sum, $1,000,000 is spent annually in the maintenance of a legal department, one-half of which expense may safely be attributed to the defense and settlement of personal injury damage suits. These figures do not cover the total expense of injuries by common carriers by any means. This compilation pertains solely to the steam railroads, while the interurban electric lines and local street railway lines increase the above totals many fold. Particularly do the local street railways add enormously to the list. It is estimated that the Metropolitan Elevated of New York alone pays annually $2,000,000 for personal injuries, and has constantly on hand nearly six thousand suits of this nature. The Brooklyn Rapid Transit Company's annual personal injury budget is in the neighborhood of $1,000,000. The ease with which evidence can be purchased, and the ubiquity of the professional damage suit lawyer in the large centers of population, gives the simulator and impostor a larger percentage of successful chances than with the transcontinental railroad."

Dr. Thomas contends that the surgeon who is qualified in the negligence law is in a position to render the most effective and economic service as adjuster of personal injury claims.

"There exists to-day," says he, "in most of otherwise well-organized railroads a lack of co-ordination between the legal and surgical staffs, as a result of the one failing to grasp the importance of the technic of the other. This proposition operates with equal force conversely. It is into this breach that the medico-legal claim adjuster can step to the assistance of both departments and with economy to the company."

In fact, Dr. Pearce Bailey, who is quoted as an authority on forensic medicine, expresses the belief that "the very best adjuster that a railroad can have is a medical man with knowledge of negligence law."

In conclusion, the author submits the following recommendations to the railroad companies:

"a. The instruction of trainmen and shopmen in first aid to the injured.

"b. The incorporation in this instruction of practical points on accident law.

"c. The employment in the claim department of a medical man, skilled in theory and practice of surgery and adept in negligence law, whose duty it will be to assist and advise counsel of the road, to bring about co-operation between the legal and surgical staffs of the closest possible nature, and last but not least, to be possessed of a fund of sound sense and a personality that will enable him to deal direct with the claimant."



Probable Appearance of Vesuvius Before the Great Eruption of 79 Which Destroyed Pompeii and Herculaneum.



Vesuvius from the Harbor of Naples at the Beginning of the Outburst of 1872.

Vesuvius in a Quiescent State, Viewed from the City of Naples.

VESUVIUS: PAST AND PRESENT.

Business and Personal Wants.

READ THIS COLUMN CAREFULLY.—You will find inquiries for certain classes of articles numbered in consecutive order. If you manufacture these goods write us at once and we will send you the name and address of the party desiring the information. **In every case it is necessary to give the number of the inquiry.**

MUNN & CO.

Marine Iron Works. Chicago. Catalogue free.

Inquiry No. 8025.—Wanted, address of manufacturers of secondary electric clock movements for one minute impulse.

"U. S." Metal Polish. Indianapolis. Samples free.

Inquiry No. 8026.—For manufacturers of graduating machinery, such as is used to graduate scales, squares, etc.

Handle & Spoke Mchy. Ober Mfg. Co., 10 Bell St. Chagrin Falls, O.

Inquiry No. 8027.—Wanted, small friction and screw top tin cans, wooden mailing cases and small brushes.

I sell patents. To buy, or having one to sell, write Chas. A. Scott, 719 Mutual Life Building, Buffalo, N. Y.

Inquiry No. 8028.—For manufacturers of machine suitable for grinding divi-divi.

Metal Novelty Works Co., manufacturers of all kinds of light Metal Goods, Dies and Metal Stampings our Specialty. 43-47 S. Canal Street, Chicago.

Inquiry No. 8029.—For manufacturers of machines used to make rugs from old carpets.

Every business firm and manufacturer should get our prices on lithographing—can save you money. Stilwell, 709 Pine St., St. Louis.

Inquiry No. 8030.—For manufacturers of umbrella ribs.

The celebrated "Hornsby-Akroyd" Patent Safety Oil Engine is built by the De La Vergne Machine Company Foot of East 138th Street, New York.

Inquiry No. 8031.—For manufacturers of machinery for weighing and sealing paper packages of cereals of one and two pounds weight, and also machinery for printing on canvas bags in two colors.

Manufacturers of patent articles, dies, metal stamping, screw machine work, hardware specialties, machinery tools, and wood fiber products. Quadriga Manufacturing Company, 18 South Canal St., Chicago.

Inquiry No. 8032.—Wanted, address of companies who mold electrose or imitation hard rubber.

WANTED.—At Fort Pierre. S. D., an experienced Cement Block Manufacturer with sufficient capital to install a large plant. A good business and a warm welcome are waiting for a first-class man. None other need apply. Frank G. Fischer, President Fort Pierre Businessmen's League. Warren Young, Secretary.

Inquiry No. 8033.—For manufacturers of metallic calcium.

Inquiry No. 8034.—For manufacturers of machinery for working agricultural and road forks.

Inquiry No. 8035.—Wanted, address of manufacturer of Gardiner Gyroscope.

Inquiry No. 8036.—For manufacturers of metal as thin as tin foil or thinner.

Inquiry No. 8037.—Wanted, address of makers or patentees of apparatus or system for drying fruit, in which the air passing through is first freed of its moisture by contact with concentrated sulphuric acid, running down a series of shelves arranged in tower fashion.

Inquiry No. 8038.—For manufacturers of a sheet of substance, such as paper or fabric, one side of which is to be paraffined or oiled, and the other side of which is to be coated with a glutinous-glycerine substance.

Inquiry No. 8039.—Wanted, makers of automatic lathes for pill and ointment boxes, tack barrels, etc.

Inquiry No. 8040.—For manufacturers of stump sawing machines.

Inquiry No. 8041.—For manufacturers of emery wheels, such as are clamped on fly wheel of a sewing machine.

Inquiry No. 8042.—For manufacturers of a transfer press.

RECENTLY PATENTED INVENTIONS.

Household Utilities.

MEAT-TENDERER AND VEGETABLE-CHOPPER.—F. Bruckman, East St. Louis, Ill. The patentee's invention has reference to meat pounders and choppers and vegetable-choppers, such as used in kitchens for preparing food. The object of the invention is to produce a device of this kind which is simple in construction and which will present a plurality of blades operating simultaneously upon the food.

Machines and Mechanical Devices.

GAS-FILTER.—G. A. Stebbins, Watertown, N. Y. This patentee's invention relates to an attachment for sulfite pulp digesters. It is designed to prevent the chips from clogging up the gas outlet at the top of the digester. The inventor provides a filter comprising a perforating member through which the gas may escape and a device movable toward and from said member having means for clearing the perforations from any chips which may enter and clog the same.

ICE-CREAM FREEZER.—J. E. Dunne and C. A. Fletcher, Chicago, Ill. The invention relates to ice-cream freezers, and more particularly to those intended to be built upon a large scale. The invention further relates to various constructional improvements, whereby the capacity of the freezer is greatly increased and the apparatus is rendered more easily accessible and more readily handled than freezers as heretofore constructed.

DRILL-SHARPENING MACHINE.—J. J. Brossoit, Grand Rapids, Wis. The invention relates to a machine for repairing drills—such, for example, as those disclosed in Mr. Brossoit's former patents. The present invention relates to an improved means for moving the carriage which holds the drill and also to an improvement in the dies which are employed for striking the V-point on the drill during process of sharpening the same.

NOTE.—Copies of any of these patents will be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of this paper.

Durability and Economy in Painting.

BY ROBERT JOB, CHIEF CHEMIST PHILADELPHIA AND READING RAILROAD COMPANY.

One of the great tendencies to-day in almost every line of manufacture is toward the improvement of processes and methods. The object very often has been largely the prospect of increased output resulting from the new devices and, hence, usually an ultimate lowering of the cost of production. In face, however, of greater competition in many cases, and the generally increasing knowledge of consumers concerning the properties of materials, there has been a growing disposition to consider other things in addition to the important question of first cost. As a consequence, there is an effort upon the part of the reputable manufacturer to get the cost as low as it is compatible with maintaining good quality, relying more and more for volume of sales upon the actual merit of the goods. The tendency is to get the greatest durability that can be produced, and then to sell at a price determined by competition; but, in any event, not to sacrifice durability, since the reputation of the manufacturer and, hence, the prospect of future profit will be based ultimately upon the actual service results of the product.

The above-mentioned disposition has led, naturally, to many changes in the paint industry, since the fact is now well recognized that length of service and general durability may vary tremendously in paints of identically the same chemical composition, owing to mere differences in the physical properties of the pigment. For instance, one pure white lead paint may be much inferior to another pure white lead paint, and the cause may be found to be the less careful preparation and grinding of the one than the other. This truth was brought forcibly to our attention a number of years ago by the peculiar service of three paints which were used for a period of about ten years upon the bridges and structural work upon our lines. The study was presented in detail before the Franklin Institute and is found in its Journal of July, 1904. The essence is that three paints of closely similar composition, side by side upon bridges all over our lines, gave radically different service results, for one had a life of less than one-half of that given by another, and the third was intermediate between the others in durability. Upon studying the matter closely, we found that the differences in efficiency were due to characteristic variations in the physical properties of the pigments. The one which gave the best service was almost impalpably fine, while that which gave defective service was relatively coarse, and the third was intermediate between the others in fineness. These paints contained only about twenty-three per cent of sesquioxide of iron, as the coloring matter, and the remainder was composed of inert matter, consisting of clay, silica, and sulphate of lime. Strangely enough, also, each of the three paints was made by various manufacturers in the same mills and with practically the same amount of grinding and, consequently, the milling cost of each was closely similar, and the difference in the ultimate fineness was thus due to the greater natural fineness of the one pigment beyond that of the others. The sesquioxide of iron in the first was in the form of a soft unburned ocher mixed with clayey matter, while in the others it was calcined and the particles were harder and more difficult to crush, and there was present a larger proportion of free silica and of sulphate of lime, both of which materials resist very fine grinding. Furthermore, the one paint above referred to had a longer average service life than any of the other paints then in use upon our lines, including pure white lead, white lead-zinc oxide mixtures, and various iron oxide paints.

The deductions from this study were very clear and have been borne out by subsequent experience.

It was evident that durability did not bear any relation to the cost of the paint, since one of our cheapest paints had proved the most lasting and gave the best protection, or, in other words, a paint containing only twenty-three per cent of sesquioxide of iron, with the remainder largely clay, gave far more efficient service under the same general conditions than paints of much higher first cost. It is perfectly possible to have an exceedingly durable pigment composed, we will say, of sesquioxide of iron one hundred per cent pure, but in such case the durability would be due to the physical condition of the pigment and not to the fact that a high proportion of iron was present; for pigment of identically the same composition, that is, 100 per cent pure, but coarsely ground, would be found to have little protective value, and this entirely apart from any chemical reaction between pigment and oil.

Another teaching of these service results was that durability apparently bore no relation to the opacity of the pigment, or, to put this statement in another form, a pigment consisting of silica, clayey matter, or other inert material of low refractive power may give much longer service than that obtained with another pigment of greater capacity and, hence, of better apparent covering power. A case which occurred a number of years ago in our practice will illustrate this point:

The surface of a sandstone bridge had begun to weather somewhat, and it was desired to stop the disintegration. An ordinary paint, in the nature of the case, was unsuitable and, after trials of various materials with rather unsatisfactory results, we decided to make use of a paint composed of pure linseed oil and very fine inert matter, without any coloring. This paint, of course, was nearly transparent and did not mar the appearance of the stone, but it acted as a binder and the pigment gave excellent protection.

From the discussion above it will be evident that knowledge merely of the chemical composition of a given pigment may tell little or nothing regarding the ultimate service which may be obtained from the paint and, in order to insure satisfactory results, it is our practice to rely upon definite tests which have been found to hold the physical condition of the pigment to the quality proved desirable by service results, and to make analysis of the oil to be certain of its purity. In the case of the darker colored pigments we specify only enough inorganic coloring matter, such as sesquioxide of iron, to give the necessary opacity and the desired shade. By these means we are able to secure great relative durability at low first cost.

In the cases cited above we have seen that a comparatively small proportion of tinting matter combined with a large proportion of inert matter in good physical condition gave much better service results than did other paints in which a larger proportion of coloring material was present. In the latter instances, therefore, the excess of coloring matter beyond that required to give good covering and coloring properties, even after weathering, was of no more practical value than an equivalent proportion of any inert material of proper quality; in fact, it would be less desirable, since it would tend, as is well known, to increase the chemical action of pigment upon oil, and thus to decrease durability, merely adding to the cost of the paint without giving any useful equivalent. High-priced material may, of course, have great durability and often does have it, but in our experience selling price is at times entirely without reference to service value or to cost of production.

It is a matter of observation with us that some of the paints which have given the least satisfactory service contained a considerable proportion of inorganic coloring matter, but the defective service in one such case was due to the fact that the pigment was so coarsely ground that it settled to a hard mass in the bottom of the cans on standing over night mixed for use, and also "dragged down" from the painted surface before the oil had "set."

Also, shipments have been offered of similar material in paste form, and the pigment, owing to its coarseness, had settled to the bottom of the kegs in such a hard compact form that the paste could not have been broken down for use without running again through a mill. This pigment contained about fifty per cent sesquioxide of iron. If initially fine material had been used at the outset the pigment would have remained in suspension almost indefinitely, with only the same amount of milling; and the finer pigment, of the same composition, could have been obtained without additional cost.

Another example indicating the desirability of inert material of proper quality is given by black paint. In this pigment the proportion of actual carbon is unusually small, and no benefit ordinarily would be derived from a larger proportion, unless the paint were to be used for tinting or for other purpose in which pure coloring matter was essential. Even in the latter case no indication of its value in coloring properties would be given by the mere knowledge that the material consisted solely of the pure coloring matter, owing to the wide variation which exists in the strength of the different grades of such materials.

Our practice as regards black car paint pigment is to specify approximately ten per cent of black, the remainder being very finely divided inert matter; but in determining the coloring power of this pigment we place no reliance upon the proportion of carbon which is present, but hold the tint to a definite depth. Paint of this quality is more satisfactory in working than pure black pigment, and the results in service are equally durable and the cost is relatively low.

For many purposes, of course, dark-colored pigments are inadmissible and pure white, or the lighter shades, are desired. In such cases white lead is naturally selected as a base, owing to its opacity; but, as the composition of pure white lead varies within considerable limits, and as the physical condition of the pigment sometimes differs greatly, the mere statement of purity is by no means necessarily a reliable index of quality. Moreover, paint to-day is generally exposed to sulphur fumes, particularly upon railways and in towns and cities, and a pigment composed wholly of white lead is generally undesirable, since blackening results rapidly. A mixture with zinc oxide or with some inert pigment is more lasting, owing to slower chemical action between pigment and oil, and also the whiteness is retained for a much longer time. Paints of this type have good covering properties and give good general service.

Enough now has perhaps been said to cover some idea of the properties which we consider essential to durability and of the general characteristics which are desirable. Adulteration of paint materials, such as linseed oil, turpentine, and japan, is, unfortunately, all too prevalent, and we find it necessary, in order to secure materials fully up to our specified standards, to make a uniform practice of testing each shipment upon receipt and, by this means, bar out the grades lacking in quality.

Linseed oil may be adulterated with mineral oil, fish oil, cottonseed oil, and other materials which both lower its cost and detract from its lasting qualities. Turpentine may contain benzine or other mineral oil, and japan may be of very low strength and also adulterated with various injurious constituents. Such barefaced adulteration as this constitutes direct fraud upon the purchaser of supposedly pure materials, and should be repressed by proper legal control. There seems to exist, however, in the popular mind a good deal of misconception as to the meaning of "adulteration' as applied to paints. To our mind the word means the addition of some substance detrimen-

tal to durability or other desirable property of the paint, or the foisting upon the consumer by means of misrepresentation of some article which he does not wish to purchase and would not purchase did he know its real character. The incorrect use of the term is found when a claim is made that a mixture, say of white lead and zinc oxide, or a combination of either with a proper proportion of inert material of suitable physical properties, constitutes an "adulteration." It is an adulteration if the paint is labeled "Pure White Lead," but if the label reads "Pure White Paint" it is perfectly correct; and if the properties of the paint are good in other respects, such as fineness, purity of the linseed oil, etc., the paint, as has been explained above, would be better adapted to many kinds of service than would white lead alone and, hence, such paint would be more valuable for the purposes of the consumer than pure white lead. In such a case the term "adulterated" would be preposterous if the paint were properly labeled. Or, if we consider the structural paint to which we have referred, containing twenty-three per cent of sesquioxide of iron and seventy-seven per cent of clayey matter: In the estimation of one unacquainted with technical paint matters this material might be considered a sesquioxide of iron paint grossly adulterated with clay and of little value, and, in order to get the most durable results, such a person would be likely to select the pigment which contained the highest proportion of oxide of iron, and this pigment, as has been explained, might or might not give good service, depending upon its physical character—provided, also, of course, that the linseed oil and the dryer were of good quality and in correct proportions.

The great value of the so-called "inert" materials for paint purposes was clearly recognized by Dr. Dudley years ago, and general results everywhere since that time have fully confirmed his deductions assuming, of course, that the physical condition of the inert matter must be properly regulated in order to insure the most efficient service.

Up to this point in the discussion we have assumed that definite knowledge upon the part of the consumer has existed regarding the paints used for the various purposes: that each is bought under correctly drawn specifications, and that detailed examination is made of each shipment, to be certain that the desired quality is present. This is our invariable practice. But the question naturally arises, What course shall the small consumer take to secure the most satisfactory results? Suppose, for instance, one wishes to buy a gallon of house paint. Shall he obtain a can of "ready-mixed" paint from a dealer, or shall he buy separately his paste, oil, and japan and make the mixture himself? This field is an open one, sometimes with many pitfalls, for it is unfortunate that some of the mixed paints have little merit and, consequently, no definite course can, in the nature of the case, be specified. Our feeling, however, is that it would be safer to buy a ready-mixed compound made by a reputable manufacturer rather than purchase separately the constituents. In case of a purchase of ready-mixed paint, any difficulty or poor service would be referred directly to the manufacturer and, consequently, it would be much to the interest of the latter to put upon the market only such material as he was willing to cover by his guarantee; for if this were not done, his future sales in that locality would probably be diminished. In other words, it would be clearly to his ultimate profit to pay careful attention not merely to the composition and general quality of the pigment, but also to be certain that the linseed oil was pure and well settled, that the japan was of good strength and free from constituents injurious to durability, and that only enough japan was added to give proper character to the oil. If each of the constituents was purchased separately adulteration would be likely to be present in any, and, hence, after the application of the paint it would be a

Modern Bank Vault Construction



Round Door and Vestibule in Course of Erection for the Vault of the HARVARD TRUST COMPANY, CAMBRIDGEPORT, MASS.

The above illustration shows this enormous Burglar-Proof Round Door and Vestibule in the process of finishing, thus giving a good idea of the massiveness of our work. Also, we have in course of erection Round Door Vaults for the

TRADESMEN'S TRUST CO., Philadelphia, Pa.
CAYUGA COUNTY NATIONAL BANK, Auburn, N. Y.
EXCHANGE NATIONAL BANK, Olean, N. Y.
COMMONWEALTH TRUST CO., St. Louis, Mo.

We are also building and erecting large Burglar-Proof Vaults for the

FIRST NIGHT AND DAY BANK, New York City
MOLSON'S BANK, Montreal, Canada
THE BANK OF CALIFORNIA, San Francisco, Cal.

and scores of others of equal prominence. Our Factory equipment for building

BURGLAR-PROOF BANK AND SAFE DEPOSIT VAULTS

excels that of any other concern in the world. We bid upon light and heavy Bank Vault and Burglar-Proof work of all kinds. We have a large corps of special engineers and draughtsmen whose ability is cheerfully placed at the disposal of those desiring plans, specifications and prices.

HERRING-HALL-MARVIN SAFE COMPANY
400 Broadway, New York City

FOREIGN AND DOMESTIC AGENCIES OFFICES IN LEADING CITIES
LARGEST FIRE AND BURGLAR-PROOF SAFE BUILDERS IN THE WORLD
BUILDERS OF THE BEST BANK VAULTS BUILT



"Star" Foot and Power Screw Cutting Automatic Cross Feed Lathes

FOR FINE, ACCURATE WORK

Send for Catalogue B.

SENECA FALLS MFG. CO.
695 Water Street,
Seneca Falls, N. Y., U. S. A.

Engine and Foot Lathes

MACHINE SHOP OUTFITS, TOOLS AND SUPPLIES. BEST MATERIALS. BEST WORKMANSHIP. CATALOGUE FREE

SEBASTIAN LATHE CO., 120 Culvert St., Cincinnati, O.

Foot and Power and Turret Lathes, Planers, Shapers, and Drill Presses.
SHEPARD LATHE CO. 133 W. 2d St. Cincinnati, O.

GIANT STEAM SHOVELS

Toledo 125 Ohio, U.S.A. Vulcan Place

The Vulcan Iron Works Co.

Low Rates to California and Return Via The Nickel Plate Road.

Tickets on sale daily April 24th to May 4th. Good return limit and stopover privileges. Before arranging for your trip write A. W. ECCLESTONE, D. P. A., 385 Broadway, New York City



Igniter Dynamos

For all classes of GAS ENGINES

for make and break or jump spark systems. Our latest type price $15. Write for circular of magnetos, etc.

THE CARLISLE & FINCH CO.
233 E. Clifton Ave.
Cincinnati, O.

French Motors for Lighting Plants

The "ASTER" is the best French motor on the market for lighting houses, hotels, etc. Small, compact, simple and safe to operate. Motive power alcohol, oil or gas. 2 and 4 cylinders. Great power for small engines. Easy running. Write for illustrated Price List.

ASTER COMPANY
1591 Broadway NEW YORK CITY

Alco Acetylene Gas Burners

For House Lighting or Auto and Yacht Lamps. Look better, last longer, burn brighter, and are cheaper than all others. Price $2.10 doz.

American Lava Company, Chattanooga, Tenn.

HOME MADE DYNAMOS. — SCIENTIFIC AMERICAN SUPPLEMENTS **161** and **600** contain excellent articles with full drawings. Price 10 cents each, by mail. Munn & Company, 361 Broadway, New York City, and all newsdealers.



FOR GUNSMITHS, TOOL MAKERS, EXPERIMENTAL & REPAIR WORK, ETC.

From 9-in. to 13-in. swing. Arranged for Steam or Foot Power, Velocipede or Stand-up Treadle.
Send for Lathe Catalog.
W. F. & JNO. BARNES CO.
Established 1872.
1999 Ruby St., ROCKFORD, ILL.



THE WATERBURY Emery Grinder,

with adjustable table, for flat surface grinding and finishing, and for ordinary tool grinding.

Send for Catalogue.
BLAKE & JOHNSON
P. O. BOX 1054,
WATERBURY, CONN.



Manufacturers should investigate the **B. F. BARNES MACHINE TOOLS** before placing orders. The Tool here illustrated is our 20-inch Drill, and we have many other sizes to make a very complete line, including Multiple Spindle Drills. If interested in the latest Tools for reducing costs of production, let us tell you what we have. Ask for Catalog S.

B. F. BARNES CO. Rockford, Ill.
European Branch
149 Queen Victoria St., London, E. C.

"Economo" Emery Wheel Dresser

SIZE 12 IN.

Made of an abrasive nearly as hard as a **Black Diamond.** Will true or shape any wheels except the very hard. The "*Combination*" is a roughing tool placed in one end of "Economo." Send for circular. Dresser sent on approval.

Economo 'Combination" Dresser

INTERNATIONAL SPECIALTY CO., 360 Holden Ave., Detroit, Mich.

To Book Buyers

We have just issued a new 48-page catalogue of recently published Scientific and Mechanical Books, which we will mail free to any address on application.

MUNN & COMPANY
Publishers of SCIENTIFIC AMERICAN
361 Broadway, New York

difficult matter to fix the responsibility in case of failure. Another point in favor of the paint in ready-mixed form is that the materials would be run through the mills together and would, undoubtedly, be more uniform than if the small consumer prepared his own mixture, while also in the latter case there would be greater liability of poor results, due to excess of japan.

The entire subject of painting, particularly as applied to the protection of iron and steel, is receiving great attention upon the part of engineers. This is indicated by the very general interest taken in the work of the American Society for Testing Materials in connection with this subject, and by the activity of many manufacturers in following out various lines of investigation work at their laboratories; for it seems to be well recognized that he who aims at excellence of product through critical study of the properties necessary to obtain such service will, almost of necessity, find an increasing demand for his wares.

Reading, Pa., March 9, 1906.

INDEX OF INVENTIONS

For which Letters Patent of the United States were Issued for the Week Ending April 10, 1906.

AND EACH BEARING THAT DATE

[See note at end of list about copies of these patents.]

Acetylene chlorid, making, H. Precht	817,188
Acids and ketones, making carbon, H. S. Blackmore	817,690
Acids, making dialkylbarbituric, M. Conrad	817,159
Adhesive applying device, O. Hesser	817,559
Agricultural implement, C. D. Adams	817,540
Air and gas engine, A. O. Haney	817,706
Air ship, C. F. Page	817,442
Amusement apparatus, Carlson & Haywood	817,156
Amusement apparatus, C. I. Matson	817,381
Amusement apparatus, W. H. Strickler	817,402
Amusement device, M. Stoltz	817,401
Amusement device, C. F. Hartway	817,556
Animal shears, J. D. Scovel	817,524
Atomizer, coin controlled, P. A. Dunn	817,231
Back and bust supporter, S. Meyer	817,653
Bait, revolving spinning, J. H. Lee	817,257
Ball player's shoulder guard, foot, J. B. McCalla	817,656
Barrel, collapsible, J. H. Durant	817,420
Batteries, treating alkaline storage, T. A. Edison	817,162
Bearing, ball, B. G. Goble	817,737
Bed, folding, W. C. James	817,371
Bedstead, adjustable, E. A. Barnes	817,295
Bedsteads, crib attachment for, Beall & Guy	817,542
Belt fastener, J. Millar	817,501
Benzoylalkylaminoet hanols and making same, T. Emilewicz	817,164
Bicycles, power-transmitting mechanism for, L. Combet	817,225
Bleaching composition, A. E. Nienstadt	817,267
Blouse, A. G. Huth	817,172
Boiler stay bolt, N. B. Jarriel	817,571
Boot and shoe manufacture, nailing, slugging, or like machine for use in, Maddison & Downs	817,179
Boot and shoe tacking machine, E. Nolle	817,660
Boots and shoes, apparatus for rubbing or treeing, M. J. Smith	817,453
Boring tool and arbor, Kootz & Fisher	817,377
Bottle, I. F. Gordon	817,705
Bottle closure, A. M. Taylor	817,532
Bottle neck, T. A. Huffer	817,247
Bottle, non-refillable, J. Meermans	817,500
Bottle, non-refillable, A. Feraro	817,700
Bottle, self-sealing, W. A. Miller	817,181
Bottle stopper, J. Madir	817,380
Bowling alley, D. F. McCarthy	817,504
Box covering machine, G. A. Diemer	817,631
Box nailing machine, E. C. Northrup	817,509
Brake shoe, C. W. Armbrust	817,541
Braking and clutch mechanisms, cooling system for, J. F. Metten	817,180
Bread raiser, C. H. Marshall	817,499
Brick pallet, F. Bentley	817,689
Bridge, movable, T. Rall	817,516
Brush, expansible, D. J. Purdy	817,337
Brush or puff, powder, E. Chaquette	817,694
Buckle, E. A. McMillin	817,184
Buckle, detachable, M. Barabasz	817,464
Building block molding machine, L. P. Normandin	817,661
Building construction, G. F. Fisher	817,478
Bulkhead doors, hydraulic apparatus for opening and shutting, H. O. Brandt	817,691
Buoy, bell, T. Weber	817,206
Butter cutter, A. C. Hummer	817,486, 817,487
Butter patty forming machine, G. A. Walstead	817,352
Button, A. Hall	817,170
Button, W. H. Forsyth	817,311
Button, collar, G. X. Wendling	817,536
Cabinet, kitchen, C. G. Swahn	817,202
Cable or rope guide, G. Frink	817,553
Cable terminal or coupling, electric, W. & J. Y. Middleton	817,329
Cables, forming wire, C. S. Lloyd	817,328
Calendar, pencil tip, F. J. Mathein	817,651
Camera, pocket, F. Heath	817,243 to 817,245
Camera support, H. L. Wheeler	817,207
Can cover lining machine, J. Brenzinger	817,154
Candle holder, A. Schluter, Jr.	817,394
Candy forming machine, J. A. Hollowell	817,563
Cane and stool, combined walking, W. R. Jones	817,324
Canopy tops, means for attaching, W. C. Rands	817,517
Cap, O. D. Shaw	817,343
Capsule filling apparatus, C. C. Boykin	817,622
Car bolster, trussed, A. Stucki	817,403
Car controlling device, electric, J. H. K. McCollum	817,264
Car coupling, W. A. Engel	817,307
Car coupling, H. N. Poynton	817,665
Car derailer, W. Roach	817,518
Car draft gear, railway, L. P. Mather	817,433
Car fender, safety, F. Cushman	817,299
Car fender, street, D. Houlahan	817,320
Car rail hose bridge, J. S. Heaton	817,558
Car step, folding, T. G. Clifford	817,224
Car storm curtain, open, M. E. Holden	817,562
Car wheel, J. Taylor	817,454
Car wheel, P. J. Garrison	817,636
Car wheel jack stand, L. C. Houston	817,321
Cars, electric switch for electric railway, Frank & McCaffrey	817,366
Carbureter, W. & J. Brown	817,218
Carbureter, E. E. Shiess	817,592
Carbureter, C. B. Harris	817,641



PAPER GAUGE MICROMETER

Measures thickness of paper, cardboard, sheet rubber, etc. by thousandths. Capacity 11-22 in. Cat. No. 17B of Fine Tools free.

$6.75 The L. S. Starrett Co., Athol, Mass

A. W. Faber.

Manufactory Established 1761.

Lead-Colored & Slate Pencils, Rubber Bands, Erasers, Inks, Penholders, Rulers, Water Colors, Improved Calculating Rules.

Send for descriptive Circular S.

44-60 East 23d Street, New York, N. Y.

Grand Prize, Highest Award, St. Louis, 1904.

RADIUM AND THE RADIO-ACTIVE Substances. No better or clearer scientific account has been published than that contained in SCIENTIFIC AMERICAN SUPPLEMENT **1429.** The paper presents all that is at present known about radium and the radio-active substances. Price 10 cents, by mail. Munn & Co., 361 Broadway, New York City and all newsdealers.

WARREN'S WALRUS ROOFING

Rain, snow, ice, wind, frost and summer sun are powerless against it. On a barn, a factory or a dwelling it will give perfect results for years after other roofings are worn out. Our free sample shows its value. Write for it.

WARREN CHEMICAL & MFG. CO.
18 Battery Place, New York

HASBROUCK



SAFE! SIMPLE! SILENT! SAVING!

A combination of excellence unsurpassed in the motor world. Send for illustrated catalogue, sent free.

Hasbrouck Motor Works, Inc., New London, Conn.

Convert Your Bicycle Into a Motorcycle

at small cost by attaching **the self-starting ERIE 2 H. P. Power Outfit.** This includes all parts by which anyone can easily make a **powerful, durable motorcycle.** weight 48 lbs. Bolts to frame. Speed 2 to 30 miles an hour. A hill climber. Hundreds in use. Send stamp for outfit catalogue.

MOTORCYCLE EQUIPMENT CO., Hammondsport, N. Y.

1906 THOMAS AUTO-BI



Model No. 44, Price $145

Three Horse Power. Simplest motorcycle on the market. Agents wanted everywhere. Catalog free.

THE THOMAS AUTO-BI CO.
1450 Niagara Street Buffalo, N. Y.

RELIABLE MARINE ENGINES



Reliability under all conditions is the characteristic of the "Lamb" Engines. Sizes from 1½ to 100 H. P. in stock. Write for catalogue.

TERRY & CO.
Managers Eastern and Foreign Branch
92 Chambers St., New York

Everything for Boat & Engine

ROTARY PUMPS AND ENGINES. Their Origin and Development.—An important series of papers giving a historical resume of the rotary pump and engine from 1588 and illustrated with clear drawings showing the construction of various forms of pumps and engines. 38 illustrations. Contained in SUPPLEMENTS **1109, 1110, 1111.** Price 10 cents each. For sale by Munn & Co. and all newsdealers.

MUD FORGET IT AND USE **WEED'S TIRE GRIPS**

Positively Stops Slipping or Skidding
They Make Bad Roads Good

Send for Booklet "S"

WEED CHAIN TIRE GRIP COMPANY
28 Moore St., New York City

Asbestos and Magnesia Products

STEAM PIPE AND BOILER COVERINGS.
ASBESTOS PACKING (For all purposes).
ASBESTOS FIRE-RESISTING CEMENTS.
ASBESTOS BUILDING MATERIALS.
"J-M" ASBESTOS ROOFING.
ASBESTOS FABRICS.
KEYSTONE HAIR INSULATOR.
ELECTRICAL SUPPLIES.

H. W. JOHNS-MANVILLE CO.

New York, Milwaukee, Chicago, Boston, Philadelphia, St. Louis, Pittsburg, Cleveland, New Orleans, Kansas City, Minneapolis, Little Rock, San Francisco, Los Angeles, Seattle, London.

ALWAYS AT WORK

Install an **Apple Battery Charger** on your auto, boat or engine, and it works whenever the motor is going, and keeps the batteries always full and ready to furnish fat, hot sparks. No ignition system is complete without it. Write today for full information.

Dayton Electrical Mfg. Co.
98 St. Clair St., Dayton, O.

JAGER Marine 4-Cycle Engines



Skillfully designed and well built. Single lever control, combining automatic carburettor with spark advance. Develops wide speed range and reliability under most trying conditions. Sizes 3 to 60 h. p. Send for catalog.

CHAS. J. JAGER CO.
Cor. High and Batterymarch Sts., Boston, Mass.

The WONDER ALTERNATOR

SOMETHING NEW

Just what you've been looking for

Only small combined alternating and direct current generator manufactured. The most interesting and useful piece of electrical apparatus ever offered. Can also be operated efficiently as a motor. Wound for any voltage up to 10. Weight 4½ lbs. Send for descriptive circulars. Agents wanted.

THE R. M. CORNWELL CO.
406 S. Salina St., Syracuse, N. Y.
434 Park Row Building, New York

The PRICE PYROMETER



eliminates guesswork. Any temperature from zero to 3000 degrees Fahr. indicated with absolute accuracy. Used in all industries. We guarantee satisfaction. Write for particulars and price, giving your requirements.

ELECTRIC DENTAL SPECIALTY CO.
2761 Euclid Ave., Cleveland, O.

METAL POLISHES.—FORMULAS FOR Putz Pomades, Pastes, Liquids, Powders and Soaps, for polishing metals, are contained in SCIENTIFIC AMERICAN SUPPLEMENT Nos. **1283, 1288** and **1289.** Price 10 cents each from this office and all newsdealers

THE EUREKA CLIP

The most useful article ever invented for the purpose. Indispensable to Lawyers, Editors, Students, Bankers, Insurance Companies and business men generally. Book marker and paper clip. Does not mutilate the paper. Can be used repeatedly. In boxes of 100 for 25c. To be had of all booksellers, stationers and notion dealers, or by mail on receipt of price. Sample card, by mail, free. Manufactured by **Consolidated Safety Pin Co.,** Box 121, **Bloomfield, N. J.**



Size No. 2.

For PIPE-THREADING or CUTTING



there is no machine on the market that can compare for ease of operation and excellence of work with

FORBES PATENT DIE STOCK

Vise is self-centering and dies are adjustable to any variation of the fittings. Parts can be duplicated at slight cost when worn out. Will thread and cut up to 12 in. pipe.

CATALOGUE FREE.

MACHINE No. 30. Range ¼-2 in. R. & L.

CURTIS & CURTIS CO.,
6 Garden St., Bridgeport, Conn.

Clear View Acetylene Searchlight



A neat, compact, self-generating, portable Searchlight of high power for yachts, launches and boats of all kinds. Useful in locating buoys, making landings, detecting obstructions, etc., should be part of every boat's equipment.

Write for Catalogue.

AMERICAN ACETYLENE STOVE CO.
503 Masonic Temp., Minneapolis, Minn.

Head and Shoulders Above 'Em All

This polishing head is fitted with a three-jawed chuck, holding up to ¼ inch. This added idea is a feature all users will appreciate.

List Price, $4.00

Our catalogue ought to be before you now. Send address.

GOODELL-PRATT COMPANY Greenfield, Mass.

Baldwin Recoil Check

For Automobiles Makes

"All Roads Ride Alike"

Saves your car and tires and permits of comfortable riding on bumpy roads. Helps your springs on smooth roads. Easily attached to any car, Free Booklet.

BALDWIN CHAIN & MFG. CO.
200 Chandler St., Worcester, Mass.



Automatic Water Supply

Most economical, reliable and efficient. If you have running water the Niagara engines will elevate 35 feet for each foot fall obtainable from spring, brook, or river, delivered to any distance. Write for catalogue.

Niagara Hydraulic Engine Co
140 Nassau St., N. Y.

Electrical Engineering

and Experimental Work of Every Description

We have every facility for producing first-class work promptly. Our factory is equipped with modern machinery throughout.

C. F. SPLITDORF
Engineering Dept. 17-27 Vandewater St., N. Y. City

DO YOU USE GRINDSTONES?

If so we can supply you. All sizes **mounted** and **unmounted,** always kept in stock. Remember, we make a specialty of selecting stones for all special purposes. *Send for catalogue "I"*

The CLEVELAND STONE CO.
2d Floor, Wilshire, Cleveland, O.

WELL DRILLING Machines

Over 70 sizes and styles, for drilling either deep or shallow wells in any kind of soil or rock. Mounted on wheels or on sills. With engines or horse powers. Strong, simple and durable. Any mechanic can operate them easily. Send for catalog.

WILLIAMS BROS., Ithaca, N. Y.

EBONITE PAINT-VARNISH

EBONITE genuinely protects. It prevents rust or decay. It excludes dampness absolutely. It is proof against acid and sulphur fumes and gases. It outlasts other compositions three times over. It won't crack and peel—its elasticity prevents that. The hottest sun can't blister it; EBONITE gives perfect results on smoke-stacks and boiler fronts.

If you have iron to coat, buildings to paint (where the black color doesn't matter) or roofings to be protected—EBONITE will give ideal satisfaction for years after every other coating has worn out.

Send for free sample, booklet and further information to

BUCHANAN - FOSTER CO.
452 Chestnut Street, Philadelphia, Pa.

See As the Owl Sees

The Owl sees only at night, but it's more than the average autoist can say. The SOLAR light covers both the distance and also right up in front of the car.

Other constructions go to one extreme or to the other—you get light so far ahead that you lose the location of the obstruction by the time you reach it. Or you can't penetrate the darkness far enough ahead to dodge trouble when you meet it. This combination of finely ground mirror lens and front reflector gives more light with less flicker than you can get in any other way.

BADGER BRASS MFG. CO.
KENOSHA WIS.
NEW YORK Office, 11 WARREN ST.

Regal Marine Engines



Four cycle—jump spark ignition—Automobile type. Have the smallest number of working parts consistent with a perfect operating motor. Our valves insure perfect mixture. Ignition system is like an automobile, and motor starts with one turn.

Regal Engines are fully guaranteed.

"They are Built to Run and Do It."

Our customers say we are the only manufacturers who put GOOD WORK into a SMALL ENGINE. Made in 3 types, 1 1/2, 3 and 5 H. P.—single cylinder; 8 to 15 H. P. double cylinder; 30 H. P. 4-cylinder marine. SEND FOR OUR NEW CATALOGUE No. 16—it shows all the latest designs—tells interesting things about gas engines. Mailed free.

Regal Gasoline Engine Co., Coldwater, Mich.



THE POWERS concealed in an ordinary water faucet are not realized by most of us. Water power is the cheapest form of power, as well as the most reliable and satisfactory. Our faucet water motor converts the water from your own faucet into power for a hundred useful purposes in the home and workshop and is furthermore the MOST ECONOMICAL POWER in the world. One cent a day will run it. The Little Wonder water motor is not an experiment. For three years now it has stood the test; there are several cheap imitations that copy our motor as closely as they dare, and then by the use of extravagant claims catch the unwary customer who thinks he is getting something just as good as the "Little Wonder." Investigate and you will decide that reputation is better than talk. The "Little Wonder" attaches to any water faucet. It is absolutely simple and will last for years. For **sharpening** and **grinding** edged tools, for **cleaning** and **polishing** metal and silverware, for **washing** bottles, for **beating** eggs, for **running** light machinery it is the handiest invention of recent years. 1-16 to 1-8 horse power. Outfit includes one motor, emery wheel, polishing wheel, buffing wheel, pulley wheel, sticks of silver and steel polish. Sent complete neatly boxed promptly on receipt of price $4.00 with our guarantee back of it. C. O. D. if desired. We also make larger motors up to 10 horse power, water fans and a full line of useful attachments for the Little Wonder. Write us now.

WARNER MOTOR CO. Dept. . Flatiron Bldg., N. Y. City

(Further particulars and our free descriptive booklet which we will mail you for the asking.)

I Will Make You Prosperous

If you are honest and ambitious write me today. No matter where you live or what your occupation has been, I will teach you the Real Estate business by mail; appoint you Special Representative of my Company in your town; start you in a profitable business of your own, and help you make big money at once.

Unusual opportunity for men without capital to become independent for life. Valuable book and full particulars free. Write today.

EDWIN R. MARDEN, Pres't

National Co-Operative Realty Co., 1170 Athenæum Bldg., Chicago

Fit Your Auto or Motor Boat with an Economical Carbureter



Note conical auxiliary air valve for directing air away from nozzle and saving fuel. No leather valves or rubber diaphragms to deteriorate, or metal floats to leak. Gasoline inlet positively closed by float and not by gravity. Spraying nozzle in center. Standard sizes for 1 to 2-in. inlet, $18 to $36. Satisfaction guaranteed or money refunded. Special sizes to order.

B. MORGAN, - - - Newport, R. I.

Carbureter, J. C. Lewis	817,721
Cash register, F. C. Osborn	817,725
Casting crucible steel, apparatus for, L. E. Howard	817,714
Cattle guard, Gorsuch & Bogue	817,367
Cement block molding machine, S. L. Wiltse	817,684
Cement manufacturing apparatus, C. Ellis	817,163
Cement posts, method and machine for forming, A. P. Robertson	817,670
Chain guide for pull sockets, H. Hubbell	817,485
Chains, die for curbing, F. R. Bishop	817,618
Chair. See Rail joint chair.	
Change maker, C. C. Spengler	817,530
Chuck, rock drill, T. E. Adams	817,609
Churn, J. L. Forbes	817,310
Chute, spiral, M. C. Schwab	817,341
Cigar bunching machine, A. S. Koch	817,254
Cigar rolling table and wrapper cutter, B. Liberman	817,493
Circuit breaker, automatic time, E. T. Browning	817,362
Closet seat, detachable, J. T. Baily	817,731
Clutch, L. W. G. Flynt	817,309
Clutch, electrical friction, H. A. Williams	817,730
Clutch, magnetic friction, H. A. Williams	817,210
Cock for steam cylinders, drain, S. Anderson	817,294
Coffee roaster, F. E. J. Thoreen	817,533
Coffee roaster, L. Schmidt	817,674
Collar, horse, J. Ahrendt	817,359
Column, building, T. L. Green	817,241
Combination lock, E. E. Quaintance	817,388
Compasses, ellipse, C. E. Keel	817,645
Computing machine, D. W. Shiek	817,450
Concrete piles, setting, F. Shuman	817,595
Condenser, Wheeler & Mullan	817,458
Conduits, apparatus for making fibrous, Palmer & Waterman	817,187
Contact device, A. Plecher	817,664
Conveyer, gravity, M. C. Schwab	817,278
Cooking utensil, H. Elsner	817,476
Corn crib, J. W. Engelke	817,165
Cotton chopper, G. R. Robinson	817,339
Cotton chopper, J. M. Andrews	817,613
Cotton scraper attachment, C. O. Dye	817,696
Coupling device, auxiliary, G. W. Scott	817,342
Cupola, A. Baillot	817,412
Curtain bracket, G. E. Quittmeyer	817,446
Curtain fastener, N. A. Ferres	817,477
Cuspidors, portable cabinet for, A. Heagele	817,710
Cut off, automatic, P. C. Hansen	817,707
Cutting head, W. B. Huther	817,568
Damper, J. R. McCord	817,183
Damper regulator and motor therefor, O. Saugstad	817,277
Derrick, revolving, J. A. Glancey	817,481
Die stock, adjustable, B. Borden	817,217
Disinfecting compound, J. W. England	817,166
Display apparatus, C. Jackson	817,322
Display rack, E. Bollhoefer	817,216
Display rack, O. & O. Justus	817,374
Display stand, C. H. Wheeler	817,353
Door closer and check, A. J. Rosentreter	817,393
Door frame, S. P. Stevenson	817,199
Door holding catch, G. Young	817,356
Door jamb and weather strip, C. E. Seeley	817,395
Door lock and latch, W. H. Hope	817,713
Door spring, D. S. Flory	817,168
Dough mixer, R. W. Jamieson	817,644
Dough or bread mixer, I. Stanley	817,400
Draft equalizer, transformable, W. M. Rich	817,726
Drier, J. R. Hussey	817,643
Drill. See Rock boring drill.	
Drill rod coupling, V. G. Smith	817,398
Drilling nuts and the like, machine for, M. Nelson	817,587
Drum, heating, J. M. J. Ness	817,185
Eccentric, F. M. Berger	817,617
Egg beater, G. R. Flowers	817,635
Egg beater holder, E. L. Persons	817,272
Egg, medicated nest, G. H. Jones	817,573
Electric brake, G. R. Yancey	817,606
Electric circuit controller, automatic, H. W. Leonard	817,720
Electric circuit regulation, E. A. Edwards	817,232
Electric currents passing through lamps, etc., apparatus for commuting, C. Smart	817,597
Electric furnace, C. O. Wingren	817,212
Electric light cord adjuster, J. T. & T. H. Hatherly	817,557
Electric meter, T. Duncan	817,305
Electric switch, H. E. Case	817,222
Electric time switch, C. E. Katsch	817,175
Electric time switch, J. E. Rogers	817,392
Electrical circuit controller, H. W. Leonard	817,719
Elevator safety device, F. Lundsten	817,431
Emery wheels, tool for truing, L. A. Sherman	817,528
Engine starting device, explosive, G. N. McMillan	817,266
Engines, supply controlling mechanism for gas, F. K. De la Saulx	817,193
Exhibiting machines, clutch mechanism for, J. C. Liebhardt	817,178
Facing tool, J. D. Mitchell	817,502
Feed mechanism, roller, W. M. Allen	817,151
Fence post, G. H. Kaufman	817,738
Fence post, composition, D. C. Stewart	817,282
Fender fastener, B. E. Thompson	817,204
File, account, J. O. Wilhelm	817,537
Film support, H. E. Baer	817,614
Filter, G. M. Kneuper	817,252, 817,253
Fire alarm signal box, M. J. McGowan, Jr.	817,437
Firearm, gas operated, M. F. Smith	817,198
Fireproof window, O. M. Otte	817,269
Floor dressing device, C. W. Swanson	817,407
Floor dressing machine, C. B. Wattles	817,410
Flue cutter, W. Hoffa	817,319
Folding box, H. W. Stuart	817,531
Form, garment, E. T. Palmenberg	817,511
Furnaces, fire screen for locomotive, J. Minnich	817,654
Furnaces, regulation of, E. McLean	817,438
Fuse igniting apparatus, electric, J. W. Howard	817,483
Fuses, automatic setting key for setting the firing charge rings of time, L. Beck	817,616
Gage, P. Layman	817,492
Gage line holder, F. G. Zugelder	817,357
Game apparatus, J. V. Emmerling	817,233
Game apparatus fastening device, G. H. Bailey	817,688
Game, foot ball card, L. G. Robinson	817,191
Garment fastening, P. A. C. Bates	817,615
Gas burner, A. C. Mouser	817,261
Gas igniter, automatic, A. B. Handschug	817,640
Gas making apparatus, L. P. Lowe	817,647, 817,648
Gas manufacturing and delivering apparatus, L. P. Lowe	817,649
Gas, producing, J. S. Smith	817,280
Gas producing apparatus, J. S. Smith	817,279
Gas purifier, L. P. Lowe	817,650
Gas shut-off, automatic, C. J. McCormick	817,505
Gas tubing or the like, detachable clamp for, Vogt & Hebig	817,285
Gasolene dispensing can, W. H. Robertshaw	817,391
Gear for skips, cages, and the like, safety, J. W. Campbell	817,623
Gearing, S. Graves	817,239
Ginning or burring machine, W. Youlten	817,607
Glass article molding apparatus, F. J. Mackin	817,576
Glazing or rolling machine, B. & G. McKeen	817,507
Governor, marine engine, J. W. Mowbray	817,262
Gun, gas operated machine, M. F. Smith	817,197
Hair and hat securing device, I. Frechette	817,238
Hame clasp, A. Schaefer	817,673
Hammock support, J. M. Troselj	817,534
Harrow tooth fastener, L. E. Allen	817,150
Harvester, cotton, Price & Quentell	817,666, 817,667
Harvesters, etc., guard finger for, F. Hamachek	817,425
Harvesting machine, corn, C. E. Storm	817,200
Hay rack, A. E. Cranston	817,626
Heat coil, F. B. Cook	817,160
Heating and ventilating system, W. R. McKeen, Jr.	817,658
Heating apparatus, C. F. Jenkins	817,173
Heating or cooling apparatus, surface, G. F. Jarvis	817,490
Hitching post strap, J. A. Ames	817,686
Hog trough, J. Crossin	817,627
Hoisting drum, A. E. Norris	817,268
Hoof trimmer and cleaner, J. L. Kottas	817,717
Hook. See Snap hook.	
Horse detacher, L. P. Faison	817,423
Horse detacher, J. Greece	817,424
Horse releaser, J. B. S. P. Twaha	817,599
Horseshoe, G. W. Johnson	817,323
Horseshoe, J. E. Shaffer	817,526
Horseshoe calk, W. F. Budenbach	817,155
Horseshoe calk, adjustable, T. W. J. McGann	817,578, 817,579



"The Finest Encyclopedia I Have Ever Seen."
– U. S. Senator John C. Spooner

Take, for Example

The treatment of
MINERALS and **METALS**, particularly
IRON and **STEEL** manufacture and products in

The New International Encyclopædia

and

What do you find?

That it is, in these as in hundreds of other special features, **by far the best** for the scientist, the engineer, the expert, and the student technical worker.

Admittedly supreme in the encyclopaedic field. The most recent information. The most complete information. The clearest, most concise information. The most accurate information.

"Nothing better of its kind in existence."
—New York Times.

"Far in advance of any previous American Cyclopaedia."
—W. I. Fletcher, Librarian Amherst College Library, Amherst, Mass.

"The best of its kind I have ever examined."
—Prof. Henry Houck, Pennsylvania Deputy State Superintendent of Public Instruction.

"The finest work of its kind I have ever examined."
—Emma O. Ryder, Librarian Hiram College, Hiram, O.

"The finest encyclopaedia I have ever had the pleasure to use."
—Henry G. Williams, Dean Normal College, Ohio University, Athens, O.

"I have compared it with other encyclopaedias and find none to equal it."
—Rev. O. M. Demcott, Batavia, N. Y.

"Absolutely indispensable to any reader of pretensions."
—Chattanooga Times.

"It is a great work."—*U. S. Senator Cullom.*

Partial List of Subjects in Engineering

Surveying Railways
River & Harbor Improvements
Canals, Waterworks
Hydraulic Engineering
Sanitary Science
Municipal Engineering
Parks and Playgrounds
Fireproof Construction
Safes and Safe-Deposit Vaults
Incombustible Fabrics
Fire-Proofing
Fire Protection
Mechanical Engineering
Cableway, Telpherage
Derricks
Traveling Sidewalks
Grinding & Crushing Machinery
Air Compressors
Pneumatic Dispatch
Wood-working Machinery
Mechanical Devices
Hydraulic Pressure Engine
Dynamo-Electric Machinery
Steam and Steam-Engines
Electrical Engineering
Metal-Working Machinery
Telegraphy, Submarine
Wireless Telegraphy

Every reader of this special edition ought to have this book in his home or office. The set, complete, in oak case, is in thousands of homes and offices to-day and ***highly prized.*** **Why not in yours? Our plan makes it very easy for you. Send the coupon and we will send full particulars by next mail.**

—FILL IN NAME AND ADDRESS AND SEND THIS COUPON—

GENTLEMEN:—Please send without cost to me, your pamphlet descriptive of the New International Encyclopaedia with specimen pages, colored plates, maps and information regarding prices and easy payment plan, also your 25-cent Question Booklet, free, as per your offer in this publication.

Name.....

Occupation.....

Street.....

Post Office.....

State.....

SCI. AM. 93


Leaves from the diary of the late JOHN SMITH
January 1st 1906
I am going to begin the New Year by taking out a Policy in The Prudential. No more lying awake nights and worrying days about the future for me I am going to make the future safe at least for the family.
February 4th 1906
I must take out that Prudential policy this month without fail
March 1st 1906
Was reminded by seeing an advertisement of The Prudential company, that I had not yet taken out that Policy. Must do it at once
MORNING NEWS
March 18th, 1906.
The affairs of John Smith, who passed away so suddenly a week ago, are being wound up. The estate is heavily involved. He left his family without life insurance.
THE PRUDENTIAL HAS THE STRENGTH OF GIBRALTAR
Good intentions are worthless unless carried out. There's just one time to insure—that time is today. Make the future sure by taking a Policy in
The Prudential
INSURANCE CO. OF AMERICA
Incorporated as a Stock Company by the State of New Jersey
JOHN F. DRYDEN President
Home Office NEWARK, N. J.
Write your name and address on the margin of this leaf and send it in for Information and Rates of Policies. Dept. 121

The Rapid Commercial Motor Cars
MOTOR VEHICLE CO.
"We Deliver the Goods"
Here is a Car that is Needed at Every Club, Hotel or Country Place
Our 20-passenger bus is a rapid, comfortable and economical means of transportation for guests of clubs, hotels and country places. Also a model conveyance for sight-seeing parties, and as a means of rapid transit between villages and rural communities. Rear seat may be removed to give room for baggage.
Price, 20-Passenger Car, - $2,200
" 12-Passenger Car, - 1,600
EVERY CAR GUARANTEED FOR ONE YEAR
We also make a full line of delivery cars and trucks.
For full particulars address
G. S. HENRY, Sales Manager
RAPID MOTOR VEHICLE CO. Pontiac, Mich.

DR. HENRY SMITH WILLIAMS

SCIENCE has fascinated and bored more people than anything else on earth. Everybody is ready enough to acknowledge the "marvellous wonders" and extraordinary advances of science, but they dodge everything labelled *"Scientific"* in their reading. It's the average intelligent man that revolts at that sort of thing, simply because he realizes that while he would like to know something definite about science, he hasn't the time to dig into books and articles that go over his head. But if it were possible to describe clearly and simply how science came about, how it started among our cave-dwelling ancestors, and how it has developed and subdivided itself until it has become the greatest factor in twentieth-century civilization—that would be a story worth reading—fascinating and impressive. It is this story which Dr. Henry Smith Williams has told in

A History of Science

Nothing like it has ever before been attempted. These five volumes open the eyes of the reader to a new and thorough understanding of the past and give him a better comprehension of the great realities of the present. Here is the opportunity for the busy man to clear away his hazy ideas about science, to acquire a practical knowledge of the subject in its many branches, and to read a most interesting story. It's worth thinking about.

Cut out and mail us the attached coupon and we will tell you more at length about this unique work.

HARPER & BROTHERS
PUBLISHERS
FRANKLIN SQUARE
NEW YORK CITY

Harper & Brothers New York

Please send me, free of charge, your illustrated booklet describing A HISTORY OF SCIENCE.

Name.....

Address.....

.....

Horseshoe calk, detachable, T. W. J. McGann	817,586
Horseshoe heel calk, detachable, T. W. J. McGann ....817,580 to	817,582, 817,585
Horseshoe, nailless, C. W. Crannell	817,625
Horseshoe, nailless, Gibb & Elliott	817,638
Horseshoes, detachable calk for rubber pad, T. W. J. McGann	817,584
Horseshoes, detachable heel calk for composite rubber pad, T. W. J. McGann	817,583
Hose supporter, Sturm & Silverstein	817,201
Inclined elevator, J. W. Reno	817,338
Inhaler, G. F. Hartz	817,708
Injector, E. Blauhorn	817,620
Insecticide, A. Schulz	817,194
Insulating screw shell, H. Hubbell	817,484
Invalid moving apparatus, L. Garaghty	817,703
Ironing board, J. F. Siebenthal	817,596
Jar attachment, J. H. Johnson	817,572
Journal bearing, C. Skidmore	817,676
Journal box, G. L. Harvey	817,427
Journal box, M. H. Whalen	817,683
Key fastener, W. T. Easterday	817,697
King bolt, T. W. Donahoo	817,303
Kitchen window, I. M. Thompson, reissue	12,471
Knife casing, E. Kaufmann	817,250
Ladder and bracket construction, J. M. Jones	817,174
Lamp cluster, incandescent, H. Hubbell	817,642
Lamp, electric hand, H. F. Stakelbeck	817,346
Lamp, electric incandescent, W. von Bolton	817,732
Lamp or lantern, C. L. Betts	817,297
Lamps, receptacle for incandescent electric, A. P. Seymour 817,396,	817,449
Lantern globes, lever lift for, D. C. Kline	817,430
Lantern, tubular, J. E. Johnson	817,372
Lanterns, bail support for, A. R. Pritchard	817,387
Lasting boots and shoes, upper holding clamp for, J. O. Jones	817,373
Latch, W. H. Taylor	817,455
Lathes, thread cutting tool for, O. G. Simmons	817,451
Lattice, P. Jaeger	817,716
Ledger, loose leaf, L. M. Landing	817,255
Lenses, machine for making bifocal, T. Mundorff	817,503
Level, spirit, N. D. Chase	817,467
Lid holding tie, A. W. Gaddum	817,312
Life buoy, J. Meller	817,652
Lifting jack, W. E. Gaston	817,637
Light reflecting and directing apparatus, Boas & Rodrigues-Ely	817,621
Lighting purposes, incandescing body for, W. von Bolton	817,734
Limb, artificial, R. Rosenkranz	817,340
Line guide, W. R. McGowen	817,723
Linotype machine, D. S. Kennedy	817,646
Liquid separator, centrifugal, G. J. Bragg	817,465
Loading apparatus, E. Ring	817,274
Lock, Turner & Hyman	817,456
Lock, M. F. Hutchison	817,567
Locomotive spark preventer, D. Drummond	817,474
Loom filling replenishing mechanism, Foerster & Corey	817,236
Loom temple, F. Ott	817,334
Loom weft replenishing mechanism, N. Foerster	817,237
Looms, feeler stop motion for automatic, Perkins & St. Laurent	817,445
Lubricating under pressure, device for, L. M. G. Delaunay-Belleville	817,629
Lubricator, G. Sloan	817,529
Magnetic actuator, D. Bacon	817,687
Magnetic separation, F. T. Snyder	817,399
Mail bag clamp, J. A. Engle	817,308
Mail box lids, device for operating, A. Seaton	817,591
Mailing box, G. A. Owen	817,186
Malt drying apparatus, E. Ellermann	817,698
Manure distributer, S. H. Garst	817,704
Measuring device for concrete mixers, J. Muir	817,436
Measuring instrument, F. L. Traut	817,205
Meat roller or wringer, B. L. Packard	817,510
Medical appliance, J. P. Whedon	817,288
Metal bending appliance, C. E. Pickrell	817,386
Metal bending machine, A. W. Heinle	817,246
Metal cutting and trimming machine, C. T. Murray	817,263
Metal plates, die for cutting out, C. B. Agar	817,611
Metals, homogeneous body of highly refractory, W. von Bolton	817,733
Metallic structure, V. J. Niele	817,508
Meter. See Electric meter.	
Mill, D. L. Adelsperger	817,610
Mineral deposits, apparatus for detecting and localizing, Daft & Williams	817,736
Molding machine, O. D. W. Inman	817,489
Molding machine, convertible, E. H. Reed	817,189
Motor spring, A. M. Lane	817,378
Motor wheel, water, B. B. Bush	817,546
Mower, lawn, W. H. Coldwell	817,157
Mud guard fastening, B. E. Thompson	817,203
Music holder, J. L. Dodge	817,550
Necktie, C. W. T. Davies	817,364
Non-siphoning trap, E. A. Cleland	817,469
Numbering and stamping machine, J. D. Humphrey	817,429
Oil engine, Rousseau & Ferris	817,671
Ore reducing furnace, H. F. Brown	817,415
Ore separator, G. Moore	817,655
Ores of the precious metals, treating, A. C. Atwater	817,411
Ores, reducing, H. F. Brown	817,414
Packing machine, J. A. Keyes	817,375
Paddle wheel, J. B. Heggem	817,711
Pail, milk, J. Lowe	817,575
Palette, artist's, D. C. Smith	817,196
Pantaloons creaser, J. Kulhawik	817,718
Paper clip, J. Kuster	817,574
Paper trimmer, A. J. Perks	817,271
Pasteurizer, C. H. Loew	817,495
Permutation lock, G. Eller	817,551
Photograph and making same, diffraction color, H. E. Ives	817,569
Photographic postal or mailing card, G. N. Pifer	817,663
Piano, self playing, G. W. Burchett	817,545
Pick, miner's, W. S. Palmer	817,512
Picture frame jointer, J. E. Braggins	817,466
Pie making machine, J. C. Hutchison	817,488
Pipe coupling, O. E. David	817,300
Pipe making machine, H. A. Williams	817,209
Pipe pulling jack, H. B. Cunningham	817,363
Pipe stem cleaner, B. F. Eshelman	817,633
Piston, E. Moran	817,330
Planter, H. P. Kline	817,376
Plastics, apparatus for molding, G. T. McIntyre	817,383
Plating, apparatus for nickel, J. W. Aylsworth	817,152
Plow, Niesz & Stewart	817,441
Plumber's clamp, R. Parker	817,513
Pneumatic motor, R. A. Norling	817,384
Pocket knife, E. Kaufmann	817,249
Polishing or buffing wheel, C. G. Backus	817,462
Post retaining band, O. Olson	817,332
Potato dropper and planter, Albright & Joseph	817,612
Pottery, saggar for baking, J. W. Lyons	817,722
Poultry appliance, E. J. Shanahan	817,448
Power transmission system, R. Williams	817,604
Preserving apparatus, T. Widdop	817,208
Press, R. B. Campbell	817,735
Printing and issuing machine, ticket, Eastman & Hawley	817,421
Printing press, J. E. Roy	817,726
Printing presses and other machines, reciprocating bed actuating apparatus for, A. Anderson	817,215
Printing, tapestry yarn, B. H. Gledhill	817,313
Propeller wheel, A. H. Little	817,494
Propeller wheel, reversible, F. M. Spaulding	817,728
Pulley, belt, D. T. McNiel	817,439
Pulley housing, sheet metal, P. Dosch	817,228
Pulley, loose, R. C. Nugent	817,724
Pump, compound air, H. Wixon	817,538
Pump, oil, L. M. G. Delaunay-Belleville	817,630
Pump, oil well, R. E. Bole	817,543
Pump operating mechanism, W. Goble	817,639
Pump rod equalizing device, J. D. Shipman	817,675
Punching and printing system, E. C. Albree	817,291
Pushing device, L. N. Brouillard	817,693
Rack and pinion mechanism, J. C. Hames	817,369
Radiator, J. V. Washburne	817,287
Radiator, F. Briscoe	817,692
Radiator valve union nipple wrench, Dukerschien & Engle	817,695
Rail chair and joint combined, J. Joynson	817,325
Rail joint, J. R. Pring	817,336
Rail joint chair, H. H. Crawford	817,161
Railway block signaling, track instrument for automatic, A. J. Stecker	817,348

SORE THROAT

To prove the Efficiency of

Hydrozone

to Sore Throat Sufferers, I will send **One 25 Cent Bottle Free** to everyone sending me this advertisement with 10 cents to pay postage and packing. Hydrozone is a harmless germicide, indorsed and successfully used by leading physicians. Not genuine without my signature on label. Ask for Booklet on Treatment of Diseases. Sold by Leading Druggists. Good until May 10, 1906.

Prof. Charles Marchand

Dept. U, 63 Prince Street, New York

Do You Employ This Man In Your Factory?

If your factory is a large one, perhaps you have several of him constantly busy over Time Cards, subtracting records of the time-of-day workmen commence from time-of-day they stop work on each job or operation and transcribing the several items, posting them to the proper accounts, aiming to learn the labor cost of products.

Better swap him for this.



THE CALCULAGRAPH

can do more work; it draws no salary; its records require no subtracting and no posting.

It Makes No Clerical Errors

The Calculagraph is the *only machine in the World* capable of mechanically subtracting the time-of-day a man begins from the time-of-day he stops and printing his *actual working time.*

Let us tell you all about it.

CALCULAGRAPH COMPANY
1433 Jewelers Bldg., New York City, U.S.A.
Agents for Canada: Northern Electric & Mfg. Co., Montreal

BURNS AIR NOT MONEY.

One 'BEST' Light

Gives more Light than Six Electric Lights, or Ten Kerosene Lamps or One Hundred Candles, and Costs less than Kerosene.

Burns 90% Air 10% Gas

Air is free. The Lamp makes all the gas needed.

A beautiful, pure white, steady, safe light. No Wick! No Grease! No Smoke! No Odor! Hang or Set it anywhere. Over 100 Styles.

AGENTS WANTED

THE BEST LIGHT CO.,
87 E. 5th St., Canton, Ohio.

It Is Wonderful
The Fireless Cookstove
or HAY BOX
AND POINTS ON PURCHASING

A new book by Capt. HARRY H. SKINNER. Tells just how to make your own fireless Cookstove with little or no cost, save seven-eighths of your fuel and one-fifth of food with many recipes for its use by best practical cook in the United States employed by the Government.

Cloth bound, illustrated. Sent to any address on receipt of 25c. Circulars sent on application.

JAPAN PUBLISHING CO., Dept. B
American Tract Society Building, New York, N.Y.

"The Maxwell"

AUTOMOBILE

Sold under a positive guarantee that as good a car cannot be sold at a lower price.

The one car irrespective of price, that should be considered by every motor car buyer.

Multiple Disc Clutch. Three-Point Suspension of Motor and Transmission (Unit). Metal Bodies. No Noise. No Vibration.

16-20 H. P. Touring Car **$1,450**

10 H. P. Tourabout **$780**

Write Department 22 for Catalogue.

MAXWELL-BRISCOE MOTOR CO.

Members American Motor Car Manufacturers' Association

Main Plant: Tarrytown, N. Y.

CHICAGO PAWTUCKET

BRANCHES:

Maxwell-Briscoe, Incorporated, New York, N.Y.
Maxwell-Briscoe Chase Company, Chicago, Ill.
Fisher Automobile Company, Indianapolis, Ind.
Morrison-Tyler Motor Company, Boston, Mass.
Maxwell-Briscoe-McLeob Co., - Detroit, Mich.
Maxwell Garage, - - - Brooklyn, N. Y.
J. W. Willcox & Son, - Los Angeles, Cal.
Richard Irvin & Co., Foreign Representatives

1906 Motor Cycles

It's a beauty—

The 1906 model Merkel. Every good point of all the others. Exclusive ones of our own. Speed from 5 to 35 miles an hour, and perfectly controlled by the right-hand grip.

Lightest, strongest machine made. Flexible frame.

Gasoline supply for one hundred miles. Oil for 500 in one filling.

Binding guarantee with every machine.

Send for booklet "Motor Cycles and How To Manage Them."

Merkel Motor Co.
1092 26th Avenue
MILWAUKEE
WIS.



Will make for you

$100 A DAY

Spin sugar into cotton candy any color or flavor. Agents wanted.

BARTELL MACHINE CO.
53 W. 8th St., New York, U.S.A.

BABBITT METALS.—SIX IMPORTANT formulas. SCIENTIFIC AMERICAN SUPPLEMENT 1123. Price 10 cents. For sale by Munn & Co. and all newsdealers. Send for catalogue.

MENNEN'S BORATED TALCUM TOILET POWDER



A Positive Relief For—

CHAPPED HANDS, CHAFING and all skin troubles. "*A little higher in price perhaps than imitations, but a reason for it.*"

Delightful after shaving and after bathing. Sold everywhere, or mailed on receipt of 25c. Get Mennen's (the original). *Sample free*

Gerhard Mennen Company, - Newark, N. J.

Washburne's Patent

"O.K." PAPER FASTENERS

The "O. K." has the advantage of a tiny but mighty, indestructible piercing point, which goes through every sheet, co-acting with a small protecting sleeve to bind and hold with a bull-dog grip. No slipping. Handsome. Compact. Strong. Easily put on or taken off with the thumb and finger, can be used repeatedly, and they always work. Made of brass. Three sizes. Put up in brass boxes of 100 Fasteners each. At all enterprising stationers Send 10c. for sample box of 50, assorted sizes. Booklet free. Liberal discount to the trade.

JAMES V. WASHBURNE, Mfr. 210 E. Genesee St., Syracuse, N. Y.

THE IDEAL
LAWN MOWER GRINDER

This machine will grind a lawn mower perfectly in 15 minutes, and is destined to revolutionize the whole business. Greatly improved over old models, and is now perfection. Energetic men and boys make $10 per day using it. Nothing like it on the market. For Hand or Power use. For prices, etc., address the manufacturers.

THE ROOT BROS. CO., Plymouth, Ohio

Railway coupling and drawbar, F. W. Parsons 817,444
Railway gate, W. M. Lowe..... 817,259
Railway, inclined suspended, R. B. Fageol. 817,699
Railway joint, R. B. Swank..... 817,729
Railway rail holder and tie, automatically tightening, W. H. Brown..... 817,544
Railway safety device, S. A. Gaede..... 817,702
Railway signal, J. E. Adair..... 817,685
Railway signal apparatus, W. H. & S. A. Wilson 817,459
Railway signal, automatic, J. S. Anderson. 817,293
Railway signal system, Baldwin & Foote... 817,463
Railway switching mechanism, electric, H. L. Young 817,290
Railway tie, J. Freund..... 817,169
Railways, electric signaling for trolley, E. W. Lee 817,256
Razor blade holder, J. H. Hunt..... 817,566
Razor stropping machine, J. Dugmore..... 817,230
Recuperator, R. R. Lade..... 817,326
Register. See Cash register.
Ribbon holder, R. A. Gladney..... 817,554
Rifle sight, J. N. Olson..... 817,331
Rock and ore breaking machine, E. H. Sansom 817,672
Rock boring drill, tubular, W. Besson..... 817,296
Rock crusher, Byers & Myer..... 817,298
Rolling angles, E. E. Slick..... 817,345
Rolling mill, E. E. Slick..... 817,344
Rolling screw nut blanks, machine for, Anderson & Wormald..... 817,360
Roofing, composite, G. F. Bishopric..... 817,619
Roofs, snow guard for, J. H. Fulmer..... 817,480
Rotary engine, P. Decor..... 817,472
Rotary engine, G. C. Stealey..... 817,679
Rubber heel for boots and shoes, Yahraus & Hammer 817,355
Sash balance, C. Launer 817,491
Sash center, C. J. Caley..... 817,220
Sash fastener, D. G. Saunders, Jr..... 817,521
Sash fastener, F. K. Heupel..... 817,712
Sash holder, A. Tobey..... 817,681
Sash, window, O. M. Otte..... 817,270
Saw, Brown & Hirsch 817,361
Saw set, R. E. Poindexter..... 817,514
Saw setting machine, C. Napier..... 817,440
Sawing machine, J. A. Cummiskey..... 817,628
Sawing machine, log, D. A. Lunt..... 817,496
Scales, scale-beam for weighing, I. Hirsch. 817,428
Scraper, foot, G. F. Hibner..... 817,171
Screens, guide strip for sliding, H. W. & W. W. Watson 817,409
Segmental rack, W. H. Voss..... 817,286
Semaphore, C. H. Williams..... 817,603
Sewing machine, E. F. Durand..... 817,475
Sewing machine feed, W. Duchemin..... 817,304
Shaft, flexible, J. K. Stewart..... 817,283
Sharpener, knife, A. L. Davis..... 817,226
Sharpener, razor, H. P. Fowler..... 817,479
Shingle machine, Kratsch & Dauber..... 817,177
Shipping box or crate, C. D. Rice..... 817,669
Shock loader, W. Heckart..... 817,370
Shoe dipping machine, J. H. Wall..... 817,408
Sickles, water distributer for, Scott & Watson 817,523
Sieving apparatus, centrifugal, H. L. Orrman 817,333
Signal system, J. H. Lynch..... 817,497
Sill and lintel machine, F. A. Borst..... 817,413
Silo, E. F. Schlichter..... 817,522
Skirt and waist retainer, M. E. Clarke..... 817,417
Slag for production of material similar to trass, etc., treatment of blast furnace, H. Colloseus 817,158
Sled, steel, Wilson & Howe..... 817,605
Sleeve, emergency knuckle, W. F. Taylor... 817,349
Sleeve protector, Cather & Buckley..... 817,416
Sliding extensible screen, A. A. Day..... 817,471
Smoking pipe, G. L. Lundin..... 817,379
Snap hook, S. Hoar..... 817,561
Soldering machine, vacuum, H. Eachus..... 817,306
Speed indicator, R. Hartmann-Kempf..... 817,555
Spinning and twisting, cap for cap, F. A. Flather 817,167
Spinning frames, thread board for, J. E. Prest 817,273
Spring, G. L. Harvey..... 817,482
Spring wheel, D. Farrand..... 817,235
Spring wheel, W. W. McKee..... 817,265
Sprocket wheel, J. M. Dodge..... 817,632
Square, carpenter's, D. Polimeni..... 817,515
Square, T, T. Zimmerman..... 817,214
Stamp, hand, L. K. Scotford..... 817,195
Stamp, self inking, Eastman & Hawley.... 817,422
Stand. See Car wheel jack stand.
Steam boiler, H. Del Mar..... 817,418
Steam separator, H. H. Humphrey..... 817,715
Stereopticon apparatus, automatic, M. H. Killen 817,251
Still, Z. E. Fiveash 817,552
Stool, V. A. Fagerstrom..... 817,234
Storage battery, J. R. Macmillan..... 817,498
Stove, F. D. Moses..... 817,182
Stoves, foot rest for, W. Reid..... 817,447
Strainer, N. E. Skinner.....817,397, 817,452
Street cleaning machine, E. S. Pearson.... 817,662
Switch point connector, Davis & Norman.. 817,365
Table, V. A. Fagerstrom..... 817,634
Tachometer, A. C. Butler..... 817,547
Tag or label, M. H. Winn..... 817,460
Tank, A. Hahn..... 817,314
Telephone apparatus and systems, privacy device and busy signal for, E. A. Reynolds 817,390
Telephone receiver support, F. F. Howe.... 817,564
Telephone receivers, head band or support for, K. M. Turner..... 817,457
Telephone system, coin controlled, E. A. Reynolds 817,389
Temple roll, I. E. Palmer 817,443
Theatrical scenic apparatus, G. A. Miller.. 817,577
Threshing machine straw rack, C. E. Whitney 817,289
Ticket holder, portable, J. D. Cantwell..... 817,624
Tide and wave motor, G. W. Hazel..... 817,317
Tide or wave motor, G. W. Hazel..... 817,318
Tire, J. C. Raymond 817,668
Tire and brake, non-slipping, J. A. Young.. 817,539
Tire, vehicle wheel, J. L. Heward..... 817,560
Tobacco, machine for loosening cut-up, J. Wojciechowski 817,354
Toy, Harding & Hoxworth 817,316
Toy, H. E. Coates..... 817,549
Train reporting system, automatic intercommunicating, E. E. Steiner 817,281
Trap, W. E. Werd 817,601
Tray for glasses, D. H. Allen.....817,148, 817,149
Tray support, F. L. Demartini..... 817,301
Trolley support and switch, overhead, B. E. Green 817,368
Trolley wheel, M. L. Amann 817,292
Truck, P. Twomey 817,350
Truck bolster, car, A. Stucki..... 817,404
Truck, brick, M. K. Sachs..... 817,520
Truck, railway car, A. Stucki..... 817,406
Truck side frame, railway car, A. Stucki.. 817,405
Trunk, J. A. H. Villmow..... 817,351
Truss for hernia, W. H. Washburn..... 817,600
Tube connection, pitot, J. A. & E. S. Cole. 817,470
Tubes, electrolytic manufacture of metal, O. Dieffenbach 817,419
Tunnels, lowering river, P. E. McDonnell, Sr. 817,657
Turbine, steam, U. A. Rutledge..... 817,590
Turn table, C. P. Mayer..... 817,434
Twine holder, E. W. Gray..... 817,240
Twine holder and cutter, H. Stolpe..... 817,598
Type writer and adding machine, combined, A. S. Dennis..... 817,302
Type writer controlling attachment, S. A. Hardman 817,242
Valve and faucet, J. Walsh, Jr..... 817,535
Valve, balanced throttle, N. S. Barr..... 817,153
Valve for water gas plants, J. Williamson. 817,211
Valve seat dressing device, D. E. Lynam... 817,260
Valve seat grinding machine, H. Meyners.. 817,435
Valve, steam, Owens & Black..... 817,385
Vehicle, J. Loepp 817,739
Vehicle brake, W. H. Smith..... 817,678
Vehicle, motor driven, O. G. A. Littmann.. 817,258
Vehicle seat suspension, motor, O. Werner. 817,682
Vending machine, O. K. Sletto..... 817,727
Vessel propelled by steam, E. C. Robinson. 817,519
Vessel trimmer, J. P. Doyle..... 817,229
Vessels, antitorpedo construction for men-of-war, W. A. Dobson..... 817,227
Veterinary pocket mouth speculum, L. McLean 817,659
Voting lever shafts, friction device for, Delavan & Fosdick 817,473
Wagon body protector, S. Huffaker..... 817,565
Wagon brake, Zwilling & Droste..... 817,358

YOUR BEST BUSINESS PARTNER—the

OLDSMOBILE

Just consider: Low first cost, low operating expense, freedom from disorders, durability in service, easy and dependable control—six convincing facts demonstrated by the Oldsmobile. Will send you six times six convincing facts on your written request. Now it's up to you.

The Oldsmobile Standard Runabout, Model B—the car as indispensable to business economy as the telephone, the typewriter or the sewing machine—is now built with either straight or curved front. Its 7 h. p. single cylinder, water-cooled motor gives efficiency without complication. Price unchanged, $650.

The Oldsmobile Palace Touring Car, Model S—an American car, the product of American brains. Send for booklet telling why this four-cylinder 28 h. p. machine can give you more style, stability and go for $2250 than any other car on the market at double the money.

The Double-Action Olds, Model L—the car with two working strokes to every revolution of the crank—is the "**proper**" thing in automobiles—the **talk** of the year. The absence of valves, guides, cams, and other intricacies attracts the novice—satisfies the expert. Its motor has only **three working parts.** It takes hills on high speed where other cars are forced into low gear. Its price with complete equipment, $1250. "Double-Action booklet" on request. It's good reading.

OLDS MOTOR WORKS

LANSING, MICH., U. S. A.

Member Association Licensed Automobile Manufacturers.

Canadian trade supplied from Canadian Factory, Packard Electric Co., Ltd., St. Catherines, Ont.

CATALOG COUPON

Kindly send me information regarding cars checked. I am interested.

Model B_____ Model S_____
Model L___ Delivery Cars___
Passenger Traffic Cars___ *S.A.3*

*Name*_____

*Address*_____

SPECIAL COUPON

We will send one of our handsome Art Calendars to every Oldsmobile owner. Fill out the following and mail at once. *S. A. 3*

Car Number_____ Model___
When and from whom purchased

_____

*Present Owner*_____

Address _____

MOTOR TALK COUPON

Enclosed find 25 cents, for which have MOTOR TALK, a magazine devoted to automobiling, sent to me for 1 year. *S. A. 3*

*Name*_____

*Address*_____

For 1 Mile or 1,000 Miles

The Type XII, Pope Toledo, is the Fastest, Most Powerful Stock Touring Car in America



35-40 h.p. Full Equipment Price $3,500

PLEASE note carefully that we say one mile or a thousand miles—Moreover, the Type XII, 35-40 h.p. Pope-Toledo, will run more miles at less cost for tires, fuel and repairs, and with less adjusting than any high powered touring car in the world. Transmission is made of the new chrome nickel steel, having a tensile strength of 225,000 pounds, and is, without question, the strongest, most silent and smoothest running transmission ever placed in an automobile. This year we have adopted the "I" Beam form of axles, drop forged in our own plant from steel having a tensile strength of 110,000 pounds. Both foot and emergency brakes act on the rear hub bands, thus relieving all brake strain and wear on the transmission. Engine throttles down to a point making it possible to drive behind a team walking, or gives the maximum efficiency of the engine all on the high gear. Catalogue of 20-25; 35-40; 40-50 and 60 h. p, Touring Cars, Limousine and Runabouts, on request.

Be Sure the name "POPE" is on Your Automobile

POPE Toledo AUTOMOBILES

Pope Motor Car Co.
Desk 2, Toledo, O.
Members A. L. A. M.
Boston, 223 Columbus Ave.
New York, 1713 Broadway
Washington, 819 14th St., N. W.

BI-PED TACK PULLER

Agents Wanted

One Foot for Matting Tacks
One Foot for Carpet Tacks

The *only* tool that lifts tacks *easily, quickly*, without damage to carpets, matting or tacks. Made of best steel, on simple lever principle—everlasting. Feet changed instantly, using only the fingers. Sent postpaid on receipt of 25 cents, also a **Kangaroo Trick Lock, Free, and a Package of Interesting Matter and Samples of Specialties.**

GENERAL SPECIALTY MFG. CO., 1029 Arcade Bldg., Phila.

Write To-Day For Our Book "Boiler Room Economy."

This book tells all about boiler scale, its causes, its danger and its remedy. It's a book which will prove of interest to everyone interested in steam generation. The **Dean Boiler Tube Cleaner**, of which de

tailed description will be found in Boiler Room Economy, is the only cleaner which will remove all scale from boiler tubes. We'll loan this cleaner to any power user for trial. The book tells all about the trial offer.

WM. B. PIERCE & CO.
319 Washington St., Buffalo, N. Y.



THE IDEAL SIGHT RESTORER

Is Your Sight Failing?

All refractive errors, muscular trouble & chronic diseases of the Eye cured by scientific MASSAGE.

Illustrated treatise with affidavit testimonials free. Address

THE IDEAL COMPANY,
239 Broadway, New York.

Washing machine, C. L. Rock	817,192
Water heater, D. Shaffer	817,525
Water heater, domestic, W. H. Roberts	817,589
Water heater, electric, F. F. Shipp	817,593
Water heater, electrical, F. F. Shipp	817,594
Water heater, gas, D. J. F. Buck	817,219
Water heating apparatus, W. S. Whitmore	817,602
Wave motor, F. Starr	817,347
Wax holder, K. Rohrdantz	817,275
Weather strip, T. S. Christie	817,223
Weighing machine, E. Cameron	817,221
Well drilling machine, J. W. Shawver	817,527
Wheel barrow, B. E. Smith	817,677
Whiffletree coupling, J. R. Pring	817,335
Whip socket, J. M. Clark	817,548
Winder, J. W. Harris	817,426
Window screen, J. W. Adams	817,461
Window, sliding, Thompson & Bentley	817,284
Wire clamp, J. A. Reising	817,588
Wire reeling truck, E. H. Jacox	817,248
Wire screen, J. M. Stewart	817,680
Wire stretcher, G. W. Riker	817,190
Wire working die, Jackson & Lee	817,570
Wood clip, G. F. Martin	817,432
Wood cutting machine, W. Merrill	817,382
Wood or other material, decorating, E. G. Adames	817,608
Wrench, W. H. Zachary	817,213
Wrench, H. C. Land	817,327
Wrench, H. M. Clark	817,468
Wrench, M. J. McGinn	817,506
Wrench, W. H. Floto	817,701
Wrench, A. Hayes	817,709
Writing or printing with metallic leaf, F. S. Hall	817,315

DESIGNS.

Automobile body, W. H. Atwood	37,952
Automobile whip socket, C. O. Sterling	37,951
Box, W. Jones	37,944
Card mount, H. A. Stone	37,945
Glass holder, J. F. Conlin	37,943
Glass, sheet, W. W. Pilkington	37,953
Illuminator, O. A. Mygatt	37,946
Inkstand, C. B. Rogers	37,941
Lamp, R. M. Dixon	37,948 to 37,950
Lamp holder, wall, J. F. Geraghty	37,947
Spoons or similar articles, handle of, S. J. Large	37,942

TRADE MARKS.

Acid phosphate of lime, powdered, Provident Chemical Works	51,357
Adzes, hatchets, and axes, Supplee Hardware Co.	51,217
Axes and hatchets, Supplee Hardware Co.	51,216
Baking powder, J. D. & R. S. Christian Co.	51,324
Baking powder, Crescent Manufacturing Co.	51,340
Bearings, bushings, and journals, metal, North American Metaline Co.	51,247
Beer, Christian Moerlein Brewing Co.	51,206
Beer, J. L. Hoerber Brewing Co.	51,293
Beer, lager, Quinn & Nolan Beverwyck Brewing Co.	51,249
Belt dressing, Stephenson Mfg. Co.	51,251
Belt dressings, Black Diamond Mfg. Co., 51,204,	51,205
Beverages, non-alcoholic carbonated, F. M. Finley	51,228
Beverages, solid salts for making, J. Personeni	51,196
Bicycles, H. Keidel	51,353
Bitters, J. Fuger	51,211
Bitters, John Bardenheier Wine & Liquor Co.	51,352
Boats, folding canvas, G. H. Winans	51,219
Boots and shoes, leather, Bentley & Olmsted Co.	51,181
Boots and shoes, leather, B. F. Reynolds	51,198
Boots and shoes, leather, A. W. Tedcastle & Co.	51,200
Brandy, corn, Charles Jacquin et Cie	51,280
Butter, Beyer Bros. Co.	51,277
Butter, E. O. Whitford Co	51,287
Cakes, J. Hochbaum	51,292
Canned fruits and vegetables, Weideman Co. 51,306,	51,307
Canned salmon, Fidalgo Island Packing Co. 51,288, 51,321,	51,322
Capsules, filled gelatin, J. R. Planten 51,355,	51,356
Card holder, G. F. Wedderburn	51,255
Cards, playing, U. S. Playing Card Co.	51,202
Cement, belt, New York Leather Belting Co.	51,246
Cement, Portland, Glens Falls Portland Cement Co.	51,235
Champagne, T. Martindale & Co	51,214
Chemical coating, Toch Brothers	51,335
Cigarette paper, C. Schutz	51,199
Cigars, E. H. Gato Cigar Co	51,225
Cigars, Havana, Havana Commercial Co., 51,237,	51,291
Coats, trousers, and vests, men's, J. Yeska	51,308
Coffee, Schwabacher Bros. & Co	51,332
Coffee, cereal, Buffalo Pure Food Co	51,315
Cordials, S. Hochstadter	51,239
Corset covers and corset waists, C. A. Powell	51,273
Corsets, Artists' Model Coat Co	51,311
Cotton duck, William E. Hooper & Sons Co. of Baltimore City	51,336
Cotton piece goods, Tremont & Suffolk Mills	51,360
Crackers, cakes, and bread, Austin Young & Co.	51,312
Croustades, F. Beaumont	51,338
Fabrics, certain named, F. S. Bisbee	51,220
Flavoring extracts, Lion Extract Co	51,327
Flour, wheat, Silverson Milling Co	51,304
Flour, wheat, O. W. Peirce Co	51,329
Germicides, vegetable, J. Hubbard & Co	51,351
Gin, S. Hochstadter	51,238
Gin, dry, Charles Jacquin et Cie	51,281
Ginger, preparation of, Frederick Brown Co.	51,289
Gloves and mittens, Joseph N. Eisendrath Co.	51,270
Gum, chewing, Frank H. Fleer & Co	51,267
Hair tonics, H. H. Johnson	51,295
Hams, shoulders, and bacon, J. & F. Schroth Pack. Co.	51,325
Hats and caps, F. Schoble & Co	51,275
Hats, stiff felt, soft felt, and straw, Denzer, Goodhart & Scheuer 51,223,	51,224
Hooks and eyes, De Long Hook & Eye Co 51,282,	51,283
Insecticides, C. E. Lacey & Co	51,241
Iron bars, rods, sheets, plates, hooping, and tires, Low Motor Co.	51,242
Knit underwear, Abraham & Straus	51,309
Lead and oxids of lead, white, National Lead Co.	51,301
Lead, white, National Lead Co. 51,244, 51,300, 51,302,	51,245 51,303
Lotions, skin, F. S. Williams & Co	51,257
Mattresses, J. L. Radermacher	51,197
Medical preparations, Black Diamond Medicine Co.	51,182
Medicinal preparation, C. D. Bradham	51,314
Medicine, certain named, Rex Chemical Co.	51,251
Medicine, certain named, W. W. Gavitt Medical Co.	51,253
Medicine for diseases peculiar to females, A. O. Schmidt	51,331
Medicines for the cure of female disorders, L. E. Truman	51,201
Milk and evaporated cream, condensed, Borden's Condensed Milk Co.	51,313
Nails, horse, Capewell Horse Nail Co	51,221
Obtundent or local anesthetic, Eureka Chemical Co.	51,318
Oil for watches and clocks, lubricating, J. Wing	51,258
Oil, olive, Los Angeles Olive Growers Assn.	51,298
Packing, rod, Mulconroy Co	51,192
Paint, metallic and roofing, A. E. Coen	51,264
Paints, bronze green, J. Briggs & Co	51,278
Paper, writing, Chapin & Gould Paper Co	51,183
Pencils, Handbleistift Cie. C. Wm. Bock	51,186
Pens, fountain, Century Pen Co	51,262
Pianos, Lyon & Healy	51,190
Polishes, J. A. Wright & Co	51,240
Press board or press paper, Rogers Paper Mfg. Co.	51,330
Publication, monthly, W. Goodhue	51,290
Pulleys, sash, P. Dosch	51,207
Pulp board, A. W. Case	51,261
Punch, alcoholic, C. H. Graves & Sons	51,236
Ranges, cooking and heating stoves, Kalamazoo Stove Co.	51,297
Remedies for asthma, G. Richardson	51,215
Remedies for consumption, U. S. Chemical Co.	51,218
Remedies for skin and scalp diseases, O. J. Hartwig	51,348

It rests with our nearest representative to prove to you why

Peerless Direct Drive Motor Cars

are the finest product turned out by any automobile maker in America. And the Peerless is the only American car not excelled by the fanciest-priced car from foreign lands.

It rests with you to allow him to prove or disprove it in justice to yourself. All we can tell you on paper can't begin to prove these claims to you the way an actual examination of the Peerless, and comparison with all other cars can do—not so well as the Peerless ride that our nearest agent will take pleasure in giving you.

Our Catalogue Gives a Good Idea

of the unique mechanical features of the Peerless, and we will send it to you on request. Let us also send you a letter of introduction to our nearest representative and you can see for yourself—the Peerless car and the matchless record of Peerless achievements, we are sure will be more than enough to convince you.

THE PEERLESS MOTOR CAR CO.
38 Lisbon Street **Cleveland, Ohio**
Member A.L.A.M.



"STANDARD" Two-Speed Automatic Coaster Brake Hub

Makes wheeling a delight, eliminates the druggery. Do not waste money on experiments when you can buy a perfect attachment *all in* one hub. Our little booklet tells all about it and is mailed free. Write to-day.

THE STANDARD COMPANY - - - - Torrington, Conn.

PATTON'S IRONHIDE

THE great rust-resisting coating for structural iron and steel work, gas tanks, elevators, steel cars, bridges — anything metal exposed to corroding influences.

IRONHIDE

is impervious to the action of sulphureted hydrogen and all deleterious gases. It possesses impermeability, durability, elasticity, toughness, fineness and smoothness. It covers 25 per cent more surface than red lead and is more durable. Ready to use. Write for descriptive circulars, etc.

PATTON PAINT CO.
227 Lake Street **Milwaukee, Wis.**

$43.75 Buys This Rubber Tire Wagon

Union Quality. Fully Guaranteed. Best hickory wheels, ¾ in. **Rubber Tire,** long distance, dust proof, high arched axles; oil-tempered springs. First quality material and finish. Worth nearly double our **Factory Price.** We ship for your examination, without a cent in advance, if desired, and allow

30 DAYS FREE TRIAL

Money refunded on all purchases not satisfactory. **You save dealers' profits.** We build 150 styles of Vehicles, from $26.50 to $150.00. 50 styles Harness, $5.00 to $60.00. Write to-day for our 200-page **Illustrated Style Book. Free** for the asking.

UNION BUGGY COMPANY, **28 Saginaw Street, Pontiac, Mich.**

A Fay & Bowen Engine

Took One First and One Second Prize in the Palm Beach Races in February.

A Fay & Bowen Engine came in first in the Chicago-Mackinaw Endurance run last Summer, running the 39 hours without a single stop.

A *Reliable* Two-Cycle Machine, started without a crank.

Our unique Make-and-Break Sparker is admitted to be the best.

Write for free catalogue of Motors and Fine Boats . .

Fay & Bowen Engine Co.

80 Lake Street, GENEVA, N. Y.

A Perfect Ignition Device

For Gas and Gasoline Engines



is the Edison Battery and Spark Coil. Ensures constant speed in Gas Engines and Motor Boats. The Batteries deliver a high constant current to the coil which is specially wired to yield a hot spark every time. This combination obviates all ignition troubles. Is surer and more economical than any other sparking device. Sold by dealers everywhere. Send for name of nearest dealer, and Booklet "Battery Facts," containing valuable ignition information.

Edison Manufacturing Co.

25 Lakeside Avenue
ORANGE, N. J.

31 Union Square, New York
304 Wabash Avenue, Chicago
25 Clerkenwell Road, London, E.C.

NEW YORK SCHOOL OF
AUTOMOBILE ENGINEERS

Incorporated
147 West 56th Street, New York City
Under the personal direction of
PROF. CHAS. E. LUCKE, M. E., Ph.D.
School of Engineers, Columbia University

Departments include machine tool and forge shops assembling and test shops, and every type of motor; also laboratories completely and specially equipped to teach all component parts of automobiles.

Day and Evening Classes.
SPECIAL COURSES FOR OWNERS.

"We Analyze Everything"

At Reasonable Rates

Investigations and Researches. Processes improved. Patent litigation, etc.

MAX D. SLIMMER, Ph.D., 403 Ellsworth Bldg., Chicago

Electric Supplies, Telephones, Novelties, Dynamos, motors, fans, batteries, lamps, bells, belts, books, toys. Big catalog 4c. We undersell all. Want ag'ts. OHIO ELECTRIC WORKS, Cleveland, Ohio

EYE BENDERS

Make your eyes by using our hand power bending machines. Take stock up to 1⅜ inch and bend up to 7 inches diameter. Write to-day for catalogue.

Wallace Supply Co., 921 Garden City Blk, Chicago, Ill.

Are you interested in Patents, Model or Experimental work? Our booklet entitled

WHAT WE DO—HOW WE DO IT

will be sent to you on request.
KNICKERBOCKER MACHINE WORKS, Inc.,
8-10-12 Jones Street, New York.

Magical Apparatus.

Grand Book Catalogue. Over 700 engravings 25c. Parlor Tricks Catalogue, free.
MARTINKA & CO., Mfrs., 493 Sixth Ave., New York.

MASON'S NEW PAT. WHIP HOISTS

save expense and liability incident to Elevators.
Adopted by principal storehouses in New York & Boston
Manfd. by VOLNEY W. MASON & CO., Inc.
Providence, R. I., U. S. A.

Telegraphy

Circular free. Wonderful automatic teacher, 5 styles $2 up. OMNIGRAPH CO., Dept. 52, 39 Cortlandt St., New York.

DO YOU
Want your PATENTS Developed?

Experimentals, Models and fine instrument work. Surveying instrument repairs a specialty.
Richter & Poncet, 115 Court Street, Hoboken, N. J.
Two minutes from D. L. W. Depot

60 YEARS' EXPERIENCE

PATENTS

TRADE MARKS
DESIGNS
COPYRIGHTS &c.

Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. HANDBOOK on Patents sent free. Oldest agency for securing patents.

Patents taken through Munn & Co. receive *special notice*, without charge, in the

Scientific American.

A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, $3 a year; four months, $1. Sold by all newsdealers.

MUNN & Co. 361 Broadway, New York

Branch Office, 625 F St., Washington, D. C.

Remedies for the cure of rheumatism, J. W. Van Lissel 51,252
Remedies for the relief and cure of asthma, consumption, etc., B. C. Silver 51,367
Remedies, topical, J. F. Ballard 51,337
Remedy for catarrh, hay fever, and cold in the head, Home Remedy Co. 51,350
Remedy for certain named diseases, R. Schiffmann Co. 51,358
Remedy for malaria, chills, and fever, F. S. Ott 51,354
Remedy for skin diseases, G. A. Coleman 51,339
Remedy, liquid rheumatic, M. W. Monaghan 51,191
Ribbons, Passavant & Co 51,248
Rings, bone, Rogers & Hubbard Co 51,274
Rivets, Low Moor Co. 51,189
Roofing felt, tarred, W. H. Rankin Co 51,305
Rubber hose, Mulconroy Co 51,193, 51,194
Salves, Ward Salve Co 51,254
Sewing machines and sewing machine parts, Household Sewing Machine Co 51,212
Sheetings and drillings, Exposition Cotton Mills 51,266, 51,319, 51,320, 51,341
Sheetings and drills, Loray Mills 51,271
Sheetings and drills, cotton, K. Iwahara 51,294
Sherry, Luyties Brothers 51,213
Shirtwaists and shirtwaist suits, ladies', D. Levy & Sons Co 51,285
Shovels, scoops, and spades, Hayden Automatic & Equipment Co 51,187
Silver plated hollow ware, International Silver Co. 51,188
Soap, N. K. Fairbank Co 51,243
Soap in the form of cakes or bars, C. W. Young & Co. 51,365
Soap, toilet, Pardridge & Blackwell 51,272
Soap, toilet, C. W. Young & Co 51,366
Sodium phosphate, liquid preparation of, Voigt & Co. 51,361
Stationery, certain named articles of, E. Faber 51,227
Steel and steel bars, rods, and sheets, tool, Hawkridge Brothers 51,349
Tea, P. Desenberg & Co. 51,284
Tea, W. E. Sibley 51,333
Tin and terne plates, Follansbee Brothers Co. 51,209, 51,210, 51,229 to 51,233, 51,342 to 51,347
Toilet preparation, certain named, Kny-Scheerer Co. 51,326
Tonic, nerve and nutritive, Geo. A. Newman Co. 51,234
Tonics, E. J. Hart & Co 51,286
Tonics, iron, E. Bischoff 51,203
Tools, certain named, Armstrong Mfg. Co 51,310
Tooth paste, J. M. Grosvenor & Co 51,323
Underwaists, children's, Nazareth Waist Co. 51,328
Varnishes, David B. Crockett Co. 51,222
Varnishes, finishes, japans, and fillers, Chas. H. Gillespie & Sons 51,263
Vermuth, Charles Jacquin et Cie 51,184
Violin strings, Lyon & Healy 51,299
Wax used in shoemaking, liquid, Crown Oil & Wax Co. 51,317
Weighing machines and parts thereof, E. & T. Fairbanks & Co. 51,226
Whips, A. J. Cook 51,265
Whisky, L. Nelson 51,195
Whisky, White, Hentz & Co 51,256
Whisky, J. H. Beam 51,259
Whisky, M. J. Bligh 51,260
Whisky, P. Freiler 51,268
Whisky, Jas. R. Ross & Co 51,269
Whisky, K. A. Buckley 51,279
Whisky, W. H. Jones & Co 51,296
Whisky, G. Cohn 51,316
Whisky, Stern Brothers 51,334
Whisky, C. H. Ross & Co 51,359
Whisky, rye, Gilliams, Jones & Co 51,185
Wines, J. S. Draper 51,208
Yeast cake, Star Yeast Cake Co 51,276

LABELS.

"Kaiser Beer," for beer, Western Brewing Co. 12,780
"Kardinal," for beer, Adolf Schmidt's Kloster Brewery 12,779

PRINTS.

"Drink Pepsi-Cola," for a health drink, Pepsi-Cola Co. 1,620

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents, provided the name and number of the patent desired and the date be given. Address Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list. For terms and further particulars address Munn & Co., 361 Broadway, New York.



Chicago Drainage Canal Case

The only record taken in this famous case in which the most world-renowned sanitary, municipal engineers and bacteriologists of this and foreign countries were witnesses.

This testimony is conveniently arranged in eight 1000 page volumes and will be of intense interest to cities and all who practice the above professions. Write for further information.

HUGH STEPHENS PRINTING COMPANY
JEFFERSON CITY, MO.

A Loose Leaf Book



PERFECTLY
Flat-Opening
AND
Self-Indexing

Most convenient for price books, route books, pocket ledgers, meter books, engagement books and all forms of records which should be kept in convenient, accessible form. Better than any card index. These **"Unimatic"** books are bound in full, genuine, flexible, black leather, are **perfectly flat opening and sheets may be instantly inserted or removed from any part.**

The following sizes sent postpaid on receipt of price:

USE	No.	BINDING EDGE	SIZE OF SHEET	CAPAC. OF COVER INCHES	CAPAC. OF COVER LEAVES	COMPLETE
Vest Pocket	212	2	2 x 4	¼	50	$0.85
" "	4412	4½	4½ x 2½	¼	50	.95
Coat Pocket	612	6	6 x 2½	¼	50	1.00
" "	5312	5½	5½ x 3	½	125	1.70
" "	6312	6¾	6¾ x 3⅜	½	125	1.75
" "	7312	7⅜	7⅜ x 4½	½	125	2.10
Desk	1132	11	11 x 8½	½	125	3.90

19 other sizes carried in stock

Stock ruling: Quadrille, Unruled, Dollars and Cents, Faint Lines, Double Entry Ledger and 4-Column Price-Book Ruling.

Send for sample sheets and complete catalogue of largest line of loose-leaf devices in the world.

Sieber & Trussell Mfg. Co., 4002 Laclede Ave., St. Louis

The Solution of Perfect Sanitation



is exemplified in the SY-CLO Closet, the construction and action of which ends at once all the subtle dangers of disease raising from improper cleansing; the escape of sewer gas; the absorption of poison by the material of which common closets are made (iron for instance); and the gradual discoloration of those interior parts which furnish a prolific breeding-ground for millions of death-dealing bacilli.

The action of the SY-CLO is two-fold. Besides the copious flush of water, there is an irresistible syphonic action, which, like a powerful pump, literally **pulls** the contents through the outlet channel, cleansing, scouring, polishing as it goes, leaving the INSIDE of the pipe as clean and smooth as a china bowl. And this is a truism because the SY-CLO is solidly constructed of china —*pure white china*—without joint or break or rough place inside or out to furnish lodgment for dirt or disease germs.

Examine your closet; if it is made of enameled iron or has just an ordinary flush, discard it at the first opportunity for a SY-CLO. *Your doctor pays the bill.* If you are building a house or buyiug one, insist on SY-CLO Closets with the trade mark name burned in the china. The fact that

SY-CLO
TRADE MARK

Closets cost but little more than other closets—that, with ordinary care, they will last as long as the house in which they are installed, leaves no further excuse for sewer sickness. Ask the plumber. A book on "Household Health" mailed free, if you send the the name of your plumber.

Lavatories of every size and design made of the same material, and on the same principle, as the SY-CLO.

POTTERIES SELLING COMPANY,
Trenton, N. J.



SY-CLO Closet cut in half showing the interior construction

Note the deep water seal, making the escape of gas impossible

An Executive Mechanic Wanted

To organize and manage large farm implement factory. Knowledge of the farm implement business desirable. For the man who can make good—and spend 12 to 14 hours a day to do it if necessary — this is one of the best positions in the country. State age and experience. Write in confidence to

"MECHANIC"
First National Bank Building
Room 1726 Chicago, Ill.

LET US BE YOUR FACTORY

WRITE FOR ESTIMATE ON ANY ARTICLE YOU WANT MANUFACTURED
STAMPINGS, MODELS, EXPER. WORK
WRITE FOR FREE BOOKLET
THE GLOBE MACHINE & STAMPING CO.
970 Hamilton St., Cleveland, O.

ICE MACHINES Corliss Engines, Brewers and Bottlers Machinery. THE VILTER MFG. CO., 899 Clinton St., Milwaukee, Wis.

MODELS & EXPERIMENTAL WORK. Inventions developed. Special Machinery. E. V. BAILLARD, 24 Frankfort Street, New York.

RUBBER Expert Manufacturers Fine Jobbing Work
PARKER, STEARNS & CO., 228-229 South Street, New York

WORKING and PATENT DRAWINGS. G. M. MAYER, M.E., 1131 Monadnock Bl., Chicago, Ill.

DRYING MACHINES. S. E. WORRELL Hannibal, Mo.

THE SCHWERDTLE STAMP CO.
STEEL STAMPS, LETTERS & FIGURES.
BRIDGEPORT CONN.

Experimental & Model Work

Cir. & advice free. Wm. Gardam & Son, 45-51 Rose St, N.Y

LEARN WATCHMAKING

We teach it thoroughly in as many months as it formerly took years. Does away with tedious apprenticeship. Money earned while studying. Positions secured. Easy terms. Send for catalog.
ST. LOUIS WATCHMAKING SCHOOL, St. Louis, Mo

SOCIALISM

The most important question of the day. Get posted. Read the greatest Socialist magazine in the world. 300,000 circulation. Send 10c. silver for one year's trial.

GAYLORD WILSHIRE, Editor
"Wilshire's Magazine," 300 Black Bldg., N. Y. City

FOR SALE

150 Phonograph Spring Motors.
150 Revolving Counter Stools.
150 1¾-inch Electric Bells.
150 Pearl Push Buttons.

1814 E. 40th Street, N. E., CLEVELAND, OHIO.

THE NATIONAL MODEL WORKS.
Experimental Work, Models, Patterns, and Light Manufacturing. 85-87 Fifth Avenue, Chicago.

NOVELTIES & PATENTED ARTICLES
MANUFACTURED BY CONTRACT. PUNCHING DIES, SPECIAL MACHINERY.
E. KONIGSLOW STAMPING & TOOL WORKS, CLEVELAND, O.

INVENTORS We manufacture METAL SPECIALTIES of all kinds, to order; largest equipment; lowest prices. Send sample or model for low estimate and best expert advice **FREE**
THE EAGLE TOOL CO., Dept. A, Cincinnati, O.

STEEL TYPEWRITER TYPE
We make, or will furnish complete outfit for making, all styles. NEW YORK STENCIL WORKS, 100 Nassau Street, New York.

Merrill and Baker's **Failure**

Places in our hands their greatest publication

RIDPATH'S HISTORY OF THE WORLD

Brand new, down to date, beautifully bound in Half Morocco at

A Very Great Bargain

We will name our price only in **direct letters** to those sending us the **Coupon** below. **Tear off the Coupon, write name and address plainly and mail to us now before you forget it.** **Only $1.00** secures complete set, balance in small sums monthly. It is strongly endorsed by Ex-Presidents Harrison, Cleveland and McKinley, Jefferson Davis, Lew Wallace, Bishop Vincent; all University and College Presidents, and by the **American People, 200,000 of whom own and love Ridpath.**



S.A. 4-21-06
H. E. Sever, TREASURER
204 Dearborn St. CHICAGO

Fold here, tear out, sign and mail

Please send RIDPATH sample pages and full particulars.

NAME.....
ADDRESS.....

New York Belting and Packing Co.

LIMITED

Manufacturers of High Grade

Rubber Belting

Diaphragms, Dredging Sleeves, Emery Wheels; Air Brake, Steam, Suction and Garden Hose, etc., Mats, Matting, Interlocking Rubber Tiling. Also manufacturers of moulded and special rubber goods of every description.

Write for catalogue.

91-93 Chambers St., New York



CHARTER

Stationaries, Portables, Hoisters, Pumpers, Sawing and Boat Outfits, Combined with Dynamos.

Gasoline, Gas, Kerosene.

Send for Catalogue.

State Power Needs.

CHARTER GAS ENGINE CO., Box 148, STERLING, ILL.

What Is Daus' Tip-Top?

TO PROVE that Daus' "Tip-Top" is the best and simplest device for making **100 copies** from pen-written and **50 copies** from typewritten original, we will ship complete duplicator, cap size, **without deposit**, on **ten (10) days' trial.**

Price $7.50 less trade discount of 33⅓ per cent. or $5 Net

The Felix A. B. Daus Duplicator Co., Daus Bldg., 111 John St., New York

Scales All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 1000 useful articles, including Safes, Sewing Machines, Bicycles, Tools, etc. save Money. Lists Free CHICAGO SCALE CO., Chicago, Ill.

CRUDE ASBESTOS

DIRECT FROM MINES

PREPARED ASBESTOS FIBRE for Manufacturers use

R. H. MARTIN, OFFICE, ST. PAUL BUILDING 220 B'way, New York.



LUFKIN

TAPES AND RULES

ARE THE BEST.

For sale everywhere. Send for Catalog No. 16.

LUFKIN RULE CO.
Saginaw, Mich., U. S. A.
New York and London.

A MONEY MAKER

Hollow Concrete Building Blocks Best, Fastest, Simplest, Cheapest Machine. Fully guaranteed.

THE PETTYJOHN CO.
615 N. 6th Street, Terre Haute, Ind.

Perhaps You Want To Know



something about a particular Tool, or Tools. This 950 page, cloth-bound **Tool Catalogue No. 22** tells you all you need to know about every tool made with illustrations of each. It will be sent to your address postpaid for $1.00 which you will get back from the first $10.00 purchase you make from us. Write for it to-day.

MONTGOMERY & CO.

105 Fulton St., N. Y. City

SPENCERIAN STEEL PENS.

The STANDARD AMERICAN BRAND

FOR OVER FIFTY YEARS

Have been subjected to the test of years and are recognized for all purposes *The Best.*

SPENCERIAN PEN CO.

349 Broadway, New York.

RUST ON GUNS TOOLS & CYCLES PREVENTED BY MANNOCITIN

C. H. BESLY & CO. CHICAGO ILL. U.S.A.

15 to 21 South Clinton Street.

THE PEN WITH THE IDEAL CLIP-CAP

A-WAY WITH THE INK WELL

Waterman's Ideal Fountain Pen

The pen with the Clip-Cap

Have You Ever Figured

how much vital energy you lose every day by the repeated operation of reaching from the paper on which you are writing to the ink well! How you lose time and the thread of your thought! It amounts to tons of nervous energy, hours of time and incalculable brain fag in a year, all of which could be saved by the use of the only perfect fountain pen—WATERMAN'S IDEAL.

Sold by leading dealers in all parts of the world.

L. E. WATERMAN COMPANY
173 Broadway, New York

209 State Street, Chicago
136 St. James Street, Montreal
12 Golden Lane, London. E. C.
6 Rue de Hanovre, Paris
8 School Street, Boston
18 Geary Street, San Francisco

STEAM USERS

Rainbow Packing

The original and only genuine red sheet packing.

The only effective and most economical flange packing in existence.

Can't blow Rainbow out.

For steam, air, hot or cold water, acid and ammonia joints.

Beware of imitations.

Look for the trade mark—the word Rainbow in a diamond in black, three rows of which extend the full length of each roll.

Manufactured exclusively by

PEERLESS RUBBER MFG. CO.
16 Warren St., New York

Mullins Sheet Metal Statuary



Unequalled for Architectural Adornment

Highly artistic effects that are exceedingly durable, and that cost much less than cast or sculptured work.

Complete illustrated catalogue mailed on request.

Write for estimates on all kinds of sheet metal work.

The W. H. Mullins Co.,
203 Franklin Street
Salem, O.



Model M Light Touring Car, $950, f. o. b. Detroit (not including lamps).

Sureness of Service

Of all the reasons why the Cadillac is the car you should own, the greatest is this: *Never-failing serviceableness at a minimum of operating expense.* Whether runabout or touring car, it is an example of careful motor building—a car behind which stand the name and experience of the largest automobile establishment in the world. Every detail of workmanship and material is wrought with that exactness which accompanies superior skill and up-to-date equipment. This is why the

CADILLAC

stands pre-eminent for its dependability and economy of maintenance. Whatever your requirements, there's a Cadillac to meet them perfectly. The single-cylinder types are marvels of power and endurance; their performances are yet to be equaled by any other machines of their class. The four-cylinder cars, built upon the same rugged principles that have made the smaller types famous, combine all that could be desired for touring service.

In design the 1906 Cadillacs are strikingly beautiful; in finish they are truly works of art.

Send for Booklet N, and address of nearest dealer, who by actual demonstration, will convince you of the merits of the Cadillac.

Model K, 10 h. p. Runabout, $750
Model M, Light Touring Car, $950
~~**Model H, 30 h. p. Touring Car, $2,500**~~
Model L, 40 h. p. Touring Car, $3,750
All prices f. o. b. Detroit

CADILLAC MOTOR CAR CO.
Detroit, Mich.

Member Assn. Licensed Auto. Mfrs.



1½ h.p. engine only, $33.15
3 h. p. engine only, 44.00

DETROIT AUTO-MARINE Motor New Mode 1906

Always Right

The uncertainty of running is all taken out in the building.

The breakdown habit has been overcome by following scientific lines of construction proven by practice to be correct.

We take no chances and allow no guesswork to enter into their make-up.

All materials are tested for soundness and strength on a testing machine and the engines warranted to do all we claim for them. We are making 10,000 Auto Marine Gasoline Engines this year, manufacturing the motor complete from foundry to finished engine, not merely assembling parts made in various factories, and that is why we are able to sell a first-class motor with a guarantee at

1½ H. P., $33.15. Engine only
3 H. P. will develop 4 H. P., $44.00. Engine only

Catalog with full information 1 to 20 H. P. Motors for the asking.

DETROIT AUTO MARINE CO.
75 E. Congress St., Detroit, Mich.
95 Liberty Street, New York
The Bourse, Philadelphia

The only builders of Auto Marine Engines in the World

Mullins Steel Boats

Motor Boats, Row Boats, Hunting and Fishing Boats

built of steel with air chambers in each end like a life boat. Faster, more buoyant, practically indestructible, don't leak, dry out and are absolutely safe. **They can't sink.** No calking, no bailing, no trouble. Every boat is guaranteed. Highly endorsed by sportsmen. The ideal boats for pleasure or sport. Catalogue describing our complete line of craft sent free on request.

The W. H. Mullins Co., 118 Franklin Street, Salem, Ohio.



YOUR OWN ELECTRIC LIGHT PLANT.

We have Standard Complete Outfits for any size place, summer homes, residences, launches, yachts, etc. Every detail included; very best material money can buy; thoroughly practical; so simple no electrician required. **Light all the time** with our Storage Battery Outfits. **Gas, Gasoline, Kerosene** or **Steam** engines used give plenty of power for pumping water, sawing wood, refrigeration, etc.

For latest printed matter covering over a hundred outfits address

ELECTRIC DEPARTMENT

RICHARDSON ENGINEERING CO. HARTFORD, CONN.

YOUR TIRE EXPENSE IS SIMPLY A MATTER OF FIRST COST AND ORDINARY CARE IF YOU BUY **PENNSYLVANIA CLINCHERS**

WE ALLOW 20% ON YOUR OLD TIRES

PENNSYLVANIA RUBBER CO.

JEANNETTE PA.

NEW YORK, 665 BROADWAY
BOSTON, 167 OLIVER ST
PHILADELPHIA, 615 N BROAD ST.
CHICAGO, 166 LAKE ST
LONDON, 4 SNOW HILL

A Sterling Silver Cigar Cutter



that is really worth more than the price you pay for it—appreciated by every smoker. Cuts clean and never tears. Simple, unique and strong.

For One Dollar

you can have this cutter delivered to your address postpaid in any part of the United States, if your jeweller cannot supply you. Our guarantee of satisfaction goes with every sale.

The R. S. Cigar Cutter

Sent postpaid to any address on receipt of **One Dollar.**

F. H. DICKSON, 22 Hay's Bldg., Maiden Lane, N. Y.